

Round 7
Groundwater Monitoring Report
for
**Defense Reutilization and
Marketing Office**

**Naval Submarine Base
New London**
Groton, Connecticut



Northern Division
Naval Facilities Engineering Command
Contract Number N62472-90-D-1298
Contract Task Order 0267

April 2000



TETRA TECH NUS, INC.

**ROUND 7 GROUNDWATER MONITORING REPORT
FOR
DEFENSE REUTILIZATION AND MARKETING OFFICE**

**NAVAL SUBMARINE BASE - NEW LONDON
GROTON, CONNECTICUT**

**COMPREHENSIVE LONG-TERM
ENVIRONMENTAL ACTION NAVY (CLEAN) CONTRACT**


**Submitted to:
Northern Division
Environmental Branch Code 18
Naval Facilities Engineering Command
10 Industrial Highway, Mail Stop #82
Lester, Pennsylvania 19113-2090**

**Submitted by:
Tetra Tech NUS, Inc.
600 Clark Avenue, Suite 3
King of Prussia, Pennsylvania 19406-1433**

**CONTRACT NUMBER N62472-90-D-1298
CONTRACT TASK ORDER 0267**

APRIL 2000

PREPARED BY:


**MARK L. MENGEL
PROJECT MANAGER
TETRA TECH NUS, INC
PITTSBURGH, PENNSYLVANIA**

APPROVED BY:



**JOHN J. TREPANOWSKI, P.E.
PROGRAM MANAGER
TETRA TECH NUS, INC
KING OF PRUSSIA, PENNSYLVANIA**

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE NO.</u>
1.0 INTRODUCTION.....	1-1
1.1 BACKGROUND INFORMATION.....	1-1
1.1.1 Base Description.....	1-1
1.1.2 Site Description and History.....	1-1
1.1.3 Previous Investigations.....	1-2
1.2 SCOPE AND OBJECTIVE	1-5
1.3 REPORT ORGANIZATION	1-5
2.0 FIELD INVESTIGATION ACTIVITIES	2-1
2.1 WATER LEVEL MEASUREMENTS.....	2-1
2.2 GROUNDWATER SAMPLING	2-1
2.3 DECONTAMINATION AND INVESTIGATION-DERIVED WASTE.....	2-2
3.0 MONITORING RESULTS	3-1
REFERENCES	R-1

APPENDICES

A	FIELD ACTIVITIES LOG BOOK
B	TIDE TABLES
C	GROUNDWATER LEVEL MEASUREMENT SHEET
D	MONITORING INSTRUMENT CALIBRATION LOGS
E	GROUNDWATER SAMPLE LOGSHEETS AND LOW-FLOW PURGE DATA SHEETS
F	CHAIN OF CUSTODY RECORDS
G	DATA VALIDATION LETTERS AND LABORATORY DATA SHEETS

TABLES

<u>NUMBER</u>		<u>PAGE NO.</u>
2-1	Groundwater Level Measurements and Elevations	2-3
3-1	Round 7 Analytical Results Summary	3-3

FIGURES

<u>NUMBER</u>		<u>PAGE NO.</u>
1-1	Site Map	1-7
1-2	DRMO Site Plan.....	1-8
2-1	Monitoring Well Locations.....	2-5
2-2	Low Tide Potentiometric Surface Map.....	2-7
2-3	High Tide Potentiometric Surface Map.....	2-9
3-1	Positive COC Detection	3-5

1.0 INTRODUCTION

This Round 7 Groundwater Monitoring Report for the Defense Reutilization and Marketing Office (DRMO) at the Naval Submarine Base New London (NSB-NLON) in Groton, Connecticut was prepared for the U.S. Department of the Navy (Navy) by Tetra Tech NUS, Inc. (TtNUS) under the Comprehensive Long-Term Environmental Action Navy (CLEAN), Contract Number N62472-90-D-1298, Contract Task Order (CTO) 0267.

This document has been prepared in accordance with the Navy Installation Restoration Laboratory Quality Assurance Guide (Interim Guidance) of the Naval Facilities Engineering Service Center, (NFESC, February 1996).

1.1 BACKGROUND INFORMATION

1.1.1 Base Description

NSB-NLON is located in southeastern Connecticut in the Towns of Ledyard and Groton. It encompasses approximately 576 acres and lies on the east bank of the Thames River, approximately 6 miles north of Long Island Sound. NSB-NLON is bounded to the east by Connecticut Route 12, to the south by Crystal Lake Road, and to the west by the Thames River. The northern border is a low, east-southeast trending ridge extending from the Thames River to Baldwin Hill.

NSB-NLON currently provides base command for naval submarine activities in the Atlantic Ocean. It also provides housing for Navy personnel and their families and supports submarine training facilities, military offices, medical facilities, and facilities for the submarine maintenance, repair, and overhaul.

1.1.2 Site Description and History

The DRMO is adjacent to the Thames River in the northwestern section of NSB-NLON. The DRMO is the storage and collection facility for items to be sold at auctions and sales held periodically throughout the year. Figure 1-1 shows the site location within NSB-NLON, and Figure 1-2 shows the general site plan.

The DRMO was used as a major base landfill and burning ground from 1950 to 1969. The materials burned and landfilled included construction materials, combustible scrap, and other non-salvageable waste items. These materials were burned on the Thames River shoreline adjacent to the current location of the DRMO. The residue was pushed to the shoreline and partially covered.

Atlantic Environmental Service, Inc. (Atlantic) personnel reviewed archived aerial photographs of the DRMO areas part of the Phase I Remedial Investigation (RI) (Atlantic, 1992). The 1934 photographs show fill in the southern portion of the site. Fill for bulkheads and docks south of the DRMO did not exist at that time. Aerial photographs from 1951 show the land in its present configuration, except for the northwest portion, which was not filled at that time.

Atlantic personnel inspected the site on September 30, 1988. Metal and wood products were stored throughout most of the site. Buildings 479 and 355 are located within the paved area to the south and are primarily used for storage. Building 491, located in the unpaved area to the north, is used for miscellaneous storage, including batteries. Metal baling operations were performed adjacent to Building 491 on a gravel surface. Based on an inspection of the building plans, Atlantic personnel identified the presence of a former battery acid handling facility at the north section of the site, within Building 491. A large scrap yard was located north of Building 479. Submarine batteries were stored in the southeast portion of the site adjacent to the railroad tracks; no leakage was observed.

Prior to 1995, the southern half of the DRMO was covered with asphalt, most of which had deteriorated, while the northern portion was unpaved and had a gravel surface. A Time-Critical Removal Action was performed at the DRMO by OHM Remediation Services Corporation. Construction aspects of the removal action were completed in January 1995. The removal action focused on the removal of soil contaminated with lead, polycyclic aromatic hydrocarbons (PAHs), and polychlorinated biphenyls (PCBs) from the northern half of the DRMO. The spent acid tank was also removed. The site was subsequently remediated and a composite cap was placed over a majority of the central and northern portions of the site (OHM, September 1995). The cap consisted of a woven geotextile liner, a geosynthetic clay liner (GCL), and a nonwoven geotextile liner. Bituminous concrete pavement was then placed over the entire area of the composite cap. The paved (southern) portion of the site was upgraded with an additional asphalt layer.

1.1.3 Previous Investigations

1.1.3.1 Phase I RI

The Phase I RI (Atlantic, 1992) at this site included test borings and monitoring well installation, as well as, soil, surface water, and groundwater sampling. Twelve shallow surface soil samples and 12 subsurface soil samples were collected from 7 test borings and 5 monitoring well borings. Four surface soil samples were collected and analyzed. Six groundwater samples were collected from five shallow wells and one deep well. Additionally, one surface water sample was collected from the Thames River at the northern end of this site (B&R Environmental, March 1997).

Concentrations of Volatile Organic Compounds (VOCs) in the soil were generally low. Semivolatile Organic Compounds (SVOCs) were present in most soil samples collected in the former landfill area. They were predominately comprised of PAHs, many of which were detected at elevated levels. A PCB, Aroclor 1260, was detected at almost all soil sample locations. Pesticides were detected in one soil sample at elevated concentrations.

Trichloroethene and 1,2-dichloroethene were detected in groundwater at three shallow downgradient wells. SVOCs (including PAHs), pesticides, petroleum hydrocarbons, or PCBs were not detected in any wells at the DRMO site. The inorganic groundwater analysis results indicated that selenium exceeded the primary drinking water standards for three wells. No VOCs, SVOCs, pesticides, or PCBs were detected in the upgradient surface water sample. Comparison of the inorganic results for this sample with the downgradient water sample (Goss Cove) did not suggest any detectable impact on the Thames River from the DRMO based on this limited data set.

1.1.3.2 Draft Focused Feasibility Study Field Investigation

A field investigation in support of the draft Focused Feasibility Study (FFS) was performed at the DRMO site in October 1993 to better define the extent of soil contamination. Twelve surface soil samples and twelve subsurface soil samples were collected. One surface and two subsurface field duplicates were also collected. One of the borings was completed as a monitoring well (6MW8S) (B&R Environmental, March 1997).

The highest concentrations of VOCs were present in soil samples west of Building 491. SVOCs, predominately PAHs, were detected in soil across the site. PCBs (Aroclor 1254, Aroclor 1260, and Aroclor 1242) were detected at nearly all boring locations at low to high concentrations. Pesticides (DDE, DDD, DDT) were detected at many locations across the site, primarily at low concentrations; however, several locations were found to have elevated levels. Concentrations of inorganic compounds were above background at all locations. Of primary concern at the site were the high levels of lead.

1.1.3.3 Phase II RI

Five new groundwater monitoring wells (two shallow and three deep) were installed and sampled during the Phase II RI. Additionally, 4 previously installed shallow wells were sampled. Two rounds of groundwater sampling were completed and ten samples were collected during each sampling round. Three subsurface soil samples were collected during the installation of three of the new wells (B&R Environmental, March 1997).

Relatively high concentrations of multiple organic and inorganic compounds were detected in the soil matrix at the DRMO. Organic chemicals detected at high concentrations include various halogenated aliphatic compounds, PAHs, phthalate esters, Aroclor-1254, and Aroclor-1260.

The results of the Phase II RI suggested that, in spite of the fact that relatively high concentrations of some VOCs were detected in the subsurface soil, it did not appear that substantial impact on the groundwater had occurred to date. In addition to the various organic chemicals detected in soil at the DRMO, relatively high concentrations of lead still remained in soil after the Time-Critical Removal Action was conducted during the course of the Phase II RI. Surface and subsurface soil concentrations of lead ranged as high as 4,980 mg/kg and 2,140 mg/kg, respectively. In spite of the high lead concentrations in soil, only limited evidence of lead migration to the water table is evidenced by the groundwater analytical results. Additionally, the results indicated that the cap effectively minimized precipitation infiltration to the groundwater (B&R Environmental, March 1997).

1.1.3.4 Time-Critical Removal Action

A Time-Critical Removal Action was performed at the DRMO by OHM Remediation Services Corporation during the course of the Phase II RI. Construction aspects of the removal action were completed in January 1995. The removal action focused on the removal of soil contaminated with lead, PAHs, and PCBs from the northern half of the DRMO.

First, a total of 73 soil samples and two pavement samples were collected from the scrap yard area north of Building 479. Then, soil was excavated to a depth of approximately 3 feet (or to the water table if the depth to water was less than 3 feet). Approximately 4,700 tons of soil was removed. Confirmation sampling was initiated when excavation operations were approximately 75% complete. Some further excavation was subsequently performed. Residual contamination above the PRGs remained in the soil after excavation was complete due to the excavation being limited to 3 feet by the shallow water table and exceedances of the allotted time for the project (B&R Environmental, March 1997).

After the completion of removal activities, the area was backfilled with clean borrow material. A cap consisting of a woven geotextile liner, a geosynthetic clay liner (GCL), and a nonwoven geotextile liner was installed. Approximately 12 inches of crushed stone and 3 inches of asphalt were placed over the clay/geotextile cover. The remaining (paved) portion of the DRMO was also upgraded via placement of an additional asphalt layer.

1.2 SCOPE AND OBJECTIVE

The objective of this Round 7 Groundwater Monitoring Report is to present and evaluate the results of the sixth round of long-term groundwater monitoring at the DRMO site. This monitoring is being conducted to verify the effectiveness of the cap installed as part of the Time-Critical Removal Action to reduce precipitation infiltration and leaching of contaminants and to confirm that contamination is not migrating through the soil, into the groundwater, and ultimately discharging to the Thames River. This groundwater monitoring is part of the post-closure associated with the DRMO cap.


To meet this objective, five existing Phase I and Phase II RI monitoring wells and five monitoring wells installed during Rounds 1 and 2 of the DRMO Groundwater Monitoring Program were sampled and analyzed for a suite of analytes based on an evaluation of site history and previous analytical results. Sampling and analyses were performed in accordance to the Groundwater Monitoring Plan (GMP) prepared for the DRMO (B&R Environmental, February 1998).

Because this is an interim report for the seventh round of groundwater monitoring, evaluation of monitoring results is limited to a comparison of these results to the criteria identified in the DRMO GMP (B&R Environmental, February 1998).


1.3 REPORT ORGANIZATION

This report has been prepared in the following format to address the requirements for long-term groundwater monitoring at the DRMO. Section 1.0 of the report is this brief introduction including the project scope and objective. Section 2.0 describes field sampling activities. Section 3.0 presents and evaluates the analytical results from the sampling effort.

This page intentionally left blank.



P:\GIS\NLON\7363\ANNUAL APPR\DRMO SITE MAP JOB 4/6/00



P:\GIS\NLON\7363\ANNUAL\APR 10/1/00 JCS DRMO SITE PLAN LAYOUT

2.0 FIELD INVESTIGATION ACTIVITIES

Field investigation activities as part of the seventh round of groundwater monitoring included two rounds of groundwater level measurements and groundwater sampling of 10 monitoring wells. Monitoring well locations are shown on Figure 2-1. These activities were performed in accordance with the procedures and methodologies described in Section 3.0: Groundwater Monitoring System Installation and Section 4.0: Sampling and Analyses of the DRMO GMP (B&R Environmental, February 1998). A copy of the field activity log book is provided as Appendix A.

2.1 WATER LEVEL MEASUREMENTS

Water levels were measured in ten monitoring wells and one staff gage (in the Thames River). The staff gage was located at the outside edge of the storm sewer outfall leading to the Thames River, west of Building 397. The measurements were collected on January 18 and 20, 2000, within time periods of 11 minutes prior to and 11 minutes following the predicted high tide on January 20 and 17 to 44 minutes following the predicted low tide on January 18 for Smith Cove, opposite the DRMO on the Thames River. Tide tables are provided in Appendix B. Table 2-1 summarizes the groundwater measurements, and Figures 2-2 and 2-3 illustrate the potentiometric surface maps for the groundwater in the shallow aquifer during low tide and high tide, respectively. Groundwater level measurement sheets can be found in Appendix C.

2.2 GROUNDWATER SAMPLING

Ten monitoring wells were sampled during the seventh round of groundwater monitoring using low-flow purging and sampling techniques, in accordance with USEPA Region I Low-Flow Purging and Sampling Procedure GW-001.

The wells were purged prior to sampling using the dedicated bladder pumps with bottled nitrogen gas as the power source. Groundwater quality parameters, including pH, specific conductivity, temperature, dissolved oxygen, salinity, and Eh were measured during purging at 5 minute intervals using a YSI 610 DM datalogger and 6820 multi-parameter water quality monitor equipped with a flow-through cell. Turbidity was also measured using a LaMotte 2020 Turbidimeter. Calibration log sheets are found in Appendix D. Water levels were also measured during purging at 5-minute intervals. Purging continued until the above parameters stabilized. Copies of the low-flow purge data sheets are provided in Appendix E. All purge water was containerized in 55-gallon drums for off-site disposal by a disposal subcontractor, as discussed in Section 2.3.

Following purging, samples were collected directly from the discharge end of the Teflon®-lined pump tubing. The groundwater samples were collected and analyzed for VOCs, SVOCs, PAH, pesticides and PCBs, and total metals. Analytical results of the samples are discussed in Section 3.0. Copies of the sample log sheets are provided in Appendix E, and chain of custody records are provided in Appendix F.

2.3 DECONTAMINATION AND INVESTIGATION-DERIVED WASTE

All water quality and water level meters were decontaminated by rinsing with de-ionized water prior to and after use.

All investigation derived waste (IDW) (i.e., purge water) was turned over to NSB-NLON and disposed of offsite by a licensed disposal company.

TABLE 2-1

**GROUNDWATER LEVEL MEASUREMENTS AND ELEVATIONS
GROUNDWATER WATER MONITORING REPORT
DRMO, NSB-NLON, GROTON, CONNECTICUT**

Well Number	Reference Elevation ⁽¹⁾ (feet msl)	Depth to Water ⁽²⁾ (feet) LOW TIDE	Depth to Water ⁽³⁾ (feet) HIGH TIDE	Groundwater Elevation (feet msl) LOW TIDE	Groundwater Elevation (feet msl) HIGH TIDE	Well Screen Depth ⁽⁴⁾
6MW1S	8.63	7.20	3.74	1.43	4.89	Shallow
6MW2S	7.30	5.83	2.29	1.47	5.01	Shallow
6MW2D	7.85	5.44	3.85	2.41	4.00	Deep
6MW6S	12.16	8.79	8.49	3.37	3.67	Shallow
6MW6D	12.50	9.11	8.95	3.39	3.55	Bedrock
6MW9S	7.52	4.30	3.48	3.22	4.04	Shallow
6MW10S	5.19	3.58	0.35	1.61	4.84	Shallow
6MW10D	5.01	2.17	0.45	2.84	4.56	Deep
6MW11S	4.92	3.36	0.00 ⁽⁵⁾	1.56	4.92	Shallow
6MW11D	5.31	2.60	0.77	2.71	4.54	Deep
SG-01	5.67	4.31	0.70	1.36	4.97	NA

msl: mean sea level (1982 Base Traverse System)

NOTES:


- 1 Reference elevation is top of well casing (1982 Base Traverse System)
- 2 Depth to water is from top of well casing. Measured January 18, 2000.
- 3 Depth to water is from top of well casing. Measured January 20, 2000.
- 4 Well screen depths designated as shallow unconfined, deep unconfined, and bedrock groundwater.
- 5 6MW11S water level was 0.10 feet above the top of the PVC riser at time of high tide measurement.

This page intentionally left blank.

040010/P

2-5

CTO 0267




DRAFT

1123BB1Z

040010/P

2-7




DRAWN BY J. BELLONE		DATE 3/30/00		Tetra Tech NUS, Inc.		CONTRACT NUMBER		OWNER NUMBER	
CHECKED BY MLM		DATE 4/7/00		LOW TIDE POTENTIOMETRIC SURFACE MAP MONITORING WELL LOCATIONS ROUND 7 GROUNDWATER SAMPLING DRMO NSB-NLON, GROTON, CONNECTICUT		APPROVED BY Mark A. Mengel		DATE 4/7/00	
COST/SCHEDULE-AREA						APPROVED BY		DATE	
SCALE AS NOTED						DRAWING NO. FIGURE 2-2		REV 0	

DRAFT

CTO 0267

040010/P



LEGEND

- Monitoring Well
- Abandoned Monitoring Well
- Staff Gauge
- Approximate Limit of Cap
- Ground Water Flow Direction
- Potentiometric Contour (Feet MSL)

DRAWN BY J. BELLONE	DATE 3/30/00
CHECKED BY MLM	DATE 4/7/00
COST/SCHEDULE-AREA	
SCALE AS NOTED	

Tetra Tech NUS, Inc.

HIGH TIDE POTENTIOMETRIC SURFACE MAP
MONITORING WELL LOCATIONS
ROUND 7 GROUNDWATER SAMPLING
DRMO
NSB-NLON, GROTON CONNECTICUT

CONTRACT NUMBER	OWNER NUMBER
APPROVED BY <i>Mark A. Mengel</i>	DATE 4/7/00
APPROVED BY	DATE
DRAWING NO. FIGURE 2-3	REV 0

3.0 MONITORING RESULTS

The groundwater samples collected from monitoring wells 6MW1S, 6MW2S, 6MW2D, 6MW6S, 6MW6D, 6MW9S, 6MW10S, 6MW10D, 6MW11S, and 6MW11D were analyzed for Target Compound List (TCL) organic chemicals and Target Analyte List (TAL) inorganic chemicals. Monitoring focused on the following organic and inorganic chemicals of potential concern, as identified in the GMP Monitoring Plan (B&R Environmental, February 1998):

- | | | |
|------------------------------|------------------------------|------------|
| • 1,1,2,2-Tetrachloroethane | • Bis(2-ethylhexyl)phthalate | • 4,4'-DDD |
| • 1,2-Dichloroethane | • Fluoranthene | • Arsenic |
| • 1,2-Dichloroethene (total) | • Fluorene | • Barium |
| • Trichloroethene | • Naphthalene | • Cadmium |
| • Vinyl Chloride | • Phenantrene | • Chromium |
| • Benzo(a)anthracene | • Pyrene | • Copper |
| • Benzo(a)pyrene | • Heptachlor Epoxide | • Lead |
| • Benzo(b)fluoranthene | • Aroclors 1254 & 1260 | • Silver |
| • Benzo(k)fluoranthene | • Hexachlorobiphenyl | • Zinc |
| • Benzoic Acid | | |

The contaminants listed were detected in soil either at concentrations that could result in exceedances of site specific Surface Water Protection Criteria (SWPCs) or at concentrations that exceed Connecticut's Pollutant Mobility Criteria for GB groundwater.

Analytical results are summarized on Table 3-1 and the positive COC detections are shown on Figure 3-1. Table 3-1 also compares the analytical results with the primary and secondary monitoring criteria, as established in the GMP (B&R Environmental, February 1998). Chemicals exceeding either primary or secondary monitoring criteria are noted by shading. The results of this comparison may be summarized as follows:

- There were no organic and inorganic exceedances of the primary monitoring criteria, which were site-specific SWPCs using a dilution factor of 100. Additionally, there were no organic exceedances of secondary monitoring criteria, which is the Federal AWQC and the Connecticut WQS for protection of human health from consumption of aquatic organisms
- Arsenic was detected in the sample from monitoring wells 6MW10D at a concentration of 4.2 µg/L. This concentration exceeded the secondary monitoring criteria (AWQCs and WQSs for protection of human health from consumption of aquatic organisms) of 0.14 µg/L for arsenic.

- Copper was detected in the sample from monitoring well 6MW2S at a concentration of 7.5 µg/L. This concentration exceeded the secondary monitoring criterion of 2.4 µg/L, which is the Federal AWQC for the protection of aquatic life (chronic, saltwater).
- Zinc was detected in the samples from monitoring wells 6MW9S (111 µg/L), 6MW9S-D (120 µg/L), and 6MW10S (91.5 µg/L). These detections slightly exceeded the secondary monitoring criterion of 81 µg/L, which is the Federal AWQC for protection of aquatic life (chronic, saltwater).
- No other exceedances of secondary monitoring criteria were noted.

As discussed in Section 1.2, because this is only an interim report for the seventh round of groundwater monitoring, the evaluation of the analytical results is limited to the above comparison. No conclusions or recommendations are drawn from this comparison. Initial conclusions and recommendations were made in the Year 1 Summary Report. Additional conclusions and recommendations will be noted upon the completion of the second year of sampling (four rounds).

Data validation letters and laboratory data sheets are attached to this report as Appendix G.

TABLE 3-1

**ROUND 7 ANALYTICAL RESULTS SUMMARY
INTERIM GROUNDWATER MONITORING REPORT
DRMO, NSB-NLON, GROTON, CONNECTICUT
PAGE 1 OF 2**

Chemical	Primary Monitoring Criterion ⁽¹⁾	Secondary Monitoring Criterion ⁽¹⁾	6MW1S ROUND 7 01/21/00	6MW2D ROUND 7 01/20/00	6MW2S ROUND 7 01/20/00	6MW6D ROUND 7 01/18/00	6MW6S ROUND 7 01/18/00	6MW9S ROUND 7 01/19/00
VOCs (ug/L)								
1,1,2,2-TETRACHLOROETHANE	1,100	11 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	1 U	1 U	1 U
1,2-DICHLOROETHANE	29,700	99 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	1 U	1 U	1 U
CIS-1,2-DICHLOROETHENE	NA	NA	1 U	0.9 J	1 U	5	1 U	1
TRANS-1,2-DICHLOROETHENE	NA	NA	1 U	1 U	1 U	1 U	1 U	1 U
TRICHLOROETHENE	23,400	81 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	9	0.5 J	1 U
VINYL CHLORIDE	157,500	525 ⁽³⁾⁽⁴⁾	1 U	0.8 J	1 U	1 U	1 U	1 U
SVOCs (ug/L)								
BENZO(A)ANTHRACENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.17 U	0.15 U	0.15 U	0.16 U	0.15 U	0.16 U
BENZO(A)PYRENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.17 U	0.15 U	0.15 U	0.16 U	0.15 U	0.16 U
BENZO(B)FLUORANTHENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.17 U	0.15 U	0.15 U	0.16 U	0.15 U	0.16 U
BENZO(K)FLUORANTHENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.17 U	0.15 U	0.15 U	0.16 U	0.15 U	0.16 U
BENZOIC ACID	NA	NA	20 U	20 UJ	20 UJ	21 UJ	20 UJ	21 UJ
BIS(2-ETHYLHEXYL)PHTHALATE	590	5.9 ⁽³⁾⁽⁴⁾	2	2 U	2 U	2.1 U	2 U	2.1 U
FLUORANTHENE	37,000	370 ⁽³⁾⁽⁴⁾	1.1 U	1 U	1 U	1 U	1 U	1.1 U
FLUORENE	1,400,000	14,000 ⁽³⁾⁽⁴⁾	1.1 U	1 U	1 U	1 U	1 U	1.1 U
NAPHTHALENE	NA	NA	1.1 U	1 U	1 U	1 U	1 U	1.1 U
PHENANTHRENE	0.77	NA	1.1 U	1 U	1 U	1 U	1 U	1.1 U
PYRENE	1,100,000	11,000 ⁽³⁾⁽⁴⁾	1.1 U	1 U	1 U	1 U	1 U	1.1 U
Pesticides/PCBs (ug/L)								
4,4'-DDD	NA	0.00084 ⁽³⁾⁽⁴⁾	0.02 U	0.021 U	0.021 U	0.021 U	0.02 U	0.02 U
AROCLOR-1254	5.0	0.00017 ⁽³⁾⁽⁴⁾	0.2 U	0.21 U	0.21 U	0.21 U	0.2 U	0.2 U
AROCLOR-1260	5.0	0.00017 ⁽³⁾⁽⁴⁾	0.2 U	0.21 U	0.21 U	0.21 U	0.2 U	0.2 U
HEPTACHLOR EPOXIDE	0.5	0.00011 ⁽³⁾⁽⁴⁾	0.01 U	0.01 U	0.01 U	0.01 U	0.01 U	0.01 U
Inorganics (total/dissolved) (ug/L)								
ARSENIC	40	0.14 ⁽³⁾⁽⁴⁾	2.6 UJ	2.6 UJ	2.6 UJ	2.6 U	2.6 U	2.6 U
BARIUM	NA	NA	21.5	174	28.1	39.3	27.6	14.6
CADMIUM	60	NA	0.30 U	0.33 U	0.60 U	0.45 U	0.36 U	0.54 U
CHROMIUM	1,100	50 ⁽²⁾	1.0 U	2.4 U	1.0 U	1.0 U	1.0 U	1.0 U
COPPER	480	2.4 ⁽²⁾	1.3 U	3.2 U	7.5	1.3 U	1.3 U	3.0 U
LEAD	130	8.1 ⁽²⁾	1.8 UJ	1.8 U	6.1 U	1.8 U	1.8 U	1.8 U
SILVER	120	1.9 ⁽²⁾	1.1 U	1.1 UJ	1.1 UJ	1.1 UJ	1.1 UJ	1.1 UJ
ZINC	1,230	81 ⁽²⁾	4.5 J	27.0 J	36.9 J	13.3 J	3.8 U	111

NOTES:

Bold numbers denote exceedance of secondary monitoring criterion. There are no exceedances of primary monitoring criteria.

- 1 Surface Water Protection Criteria for substances in groundwater, using a site-specific dilution factor of 100.
 - 2 Federal Ambient Water Quality Criteria for protection of aquatic life (chronic, saltwater).
 - 3 Federal Ambient Water Quality Criteria for protection of human health from consumption of organisms.
 - 4 Connecticut Water Quality Criteria for protection of human health from consumption of organisms.
- J Estimated Value
R Rejected Value
U Undetected
NA Not Available

TABLE 3-1

**ROUND 7 ANALYTICAL RESULTS SUMMARY
INTERIM GROUNDWATER MONITORING REPORT
DRMO, NSB-NLON, GROTON, CONNECTICUT
PAGE 2 OF 2**

Chemical	Primary Monitoring Criterion ⁽¹⁾	Secondary Monitoring Criterion ⁽¹⁾	6MW9S (DUP) ROUND 7 01/19/00	6MW10D ROUND 7 01/18/00	6MW10S ROUND 7 01/18/00	6MW11D ROUND 7 01/19/00	6MW11S ROUND 7 01/19/00
VOCs (ug/L)							
1,1,2,2-TETRACHLOROETHANE	1,100	11 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	1 U	1 U
1,2-DICHLOROETHANE	29,700	99 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	1 U	1 U
CIS-1,2-DICHLOROETHENE	NA	NA	1 U	15	0.9 J	1 U	1 U
TRANS-1,2-DICHLOROETHENE	NA	NA	1 U	1 U	1 U	1 U	1 U
TRICHLOROETHENE	23,400	81 ⁽³⁾⁽⁴⁾	1 U	5	1 U	1 U	1 U
VINYL CHLORIDE	157,500	525 ⁽³⁾⁽⁴⁾	1 U	1 U	1 U	1 U	1 U
SVOCs (ug/L)							
BENZO(A)ANTHRACENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.16 U	0.16 U	0.15 U	0.15 U	0.16 U
BENZO(A)PYRENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.16 U	0.16 U	0.15 U	0.15 U	0.16 U
BENZO(B)FLUORANTHENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.16 U	0.16 U	0.15 U	0.15 U	0.16 U
BENZO(K)FLUORANTHENE	3.0	0.049 ⁽³⁾⁽⁴⁾	0.16 U	0.16 U	0.15 U	0.15 U	0.16 U
BENZOIC ACID	NA	NA	21 UJ	21 UJ	20 UJ	20 UJ	20 UJ
BIS(2-ETHYLHEXYL)PHTHALATE	590	5.9 ⁽³⁾⁽⁴⁾	2.1 U	2.1 U	4.1	2 U	2 U
FLUORANTHENE	37,000	370 ⁽³⁾⁽⁴⁾	1.1 U	1.1 U	1 U	1 U	1.1 U
FLUORENE	1,400,000	14,000 ⁽³⁾⁽⁴⁾	1.1 U	1.1 U	1 U	1 U	1.1 U
NAPHTHALENE	NA	NA	1.1 U	1.1 U	1 U	1 U	1.1 U
PHENANTHRENE	0.77	NA	1.1 U	1.1 U	1 U	1 U	1.1 U
PYRENE	1,100,000	11,000 ⁽³⁾⁽⁴⁾	1.1 U	1.1 U	1 U	1 U	1.1 U
Pesticides/PCBs (ug/L)							
4,4'-DDD	NA	0.00084 ⁽³⁾⁽⁴⁾	0.021 U	0.02 U	0.02 U	0.02 U	0.02 U
AROCOR-1254	5.0	0.00017 ⁽³⁾⁽⁴⁾	0.21 U	0.2 U	0.2 U	0.2 U	0.2 U
AROCOR-1260	5.0	0.00017 ⁽³⁾⁽⁴⁾	0.21 U	0.2 U	0.2 U	0.2 U	0.2 U
HEPTACHLOR EPOXIDE	0.5	0.00011 ⁽³⁾⁽⁴⁾	0.01 U	0.01 U	0.01 U	0.01 U	0.01 U
Inorganics (total/dissolved) (ug/L)							
ARSENIC	40	0.14 ⁽³⁾⁽⁴⁾	2.6 U	4.2 J	2.6 U	2.6 UJ	2.6 U
BARIUM	NA	NA	14.4	44.8	127	280	89.4
CADMIUM	60	NA	0.61 U	0.37 U	1.2 U	0.30 UJ	0.64 U
CHROMIUM	1,100	50 ⁽²⁾	1.0 U	1.0 U	1.0 U	1.0 U	1.0 U
COPPER	480	2.4 ⁽²⁾	2.9 U	1.3 U	4.9 U	1.9 U	5.0 U
LEAD	130	8.1 ⁽²⁾	1.8 U	1.8 U	1.8 U	1.8 U	2.7 U
SILVER	120	1.9 ⁽²⁾	1.1 UJ	1.1 UJ	1.1 UJ	1.1 UJ	1.1 UJ
ZINC	1,230	81 ⁽²⁾	120	77.6	91.5	8.7 J	77.4

NOTES:

Bold numbers denote exceedance of secondary monitoring criterion. There are no exceedances of primary monitoring criteria.

- 1 Surface Water Protection Criteria for substances in groundwater, using a site-specific dilution factor of 100.
 - 2 Federal Ambient Water Quality Criteria for protection of aquatic life (chronic, saltwater).
 - 3 Federal Ambient Water Quality Criteria for protection of human health from consumption of organisms.
 - 4 Connecticut Water Quality Criteria for protection of human health from consumption of organisms.
- J Estimated Value
R Rejected Value
U Undetected
NA Not Available

DRAFT

040010/P

NOTES:

- 1) UNDERGROUND UTILITY LOCATIONS ARE APPROXIMATE.
- 2) BASE MAP AND UTILITY INFORMATION FROM MAPS OF NSB-NLON AND PHASE II RI WORK PLAN (ATLANTIC, MAY 1993).



APPROXIMATE
LIMIT OF CAP

LEGEND

- Monitoring Well
- Abandoned Monitoring Well
- Staff Gauge
- Approximate Limit of Cap

DRAWN BY J. BELLONE	DATE 4/10/00
CHECKED BY MLM	DATE 4/12/00
COST/SCHEDULE-AREA	
SCALE AS NOTED	

Tetra Tech NUS, Inc.

POSITIVE COC DETECTION
ROUND 7 GROUNDWATER SAMPLING
DRMO
NSB-NLON, GROTON, CONNECTICUT

CONTRACT NUMBER 7363	OWNER NUMBER
APPROVED BY <i>Mark A. Mangel</i>	DATE 4/12/00
APPROVED BY	DATE
DRAWING NO. FIGURE 3-1	REV 0

DRAFT

1123B022

REFERENCES

(Atlantic, August 1992): Phase I Remedial Investigation Naval Submarine Base - New London, Groton, Connecticut. Atlantic Environmental Services, Inc., Colchester, CT.

(Atlantic, March 1995): Action Memorandum for the Defense Reutilization and Marketing Office and the Spent Acid Storage and Disposal Area, Installation Restoration Program. Atlantic Environmental Services, Inc., Colchester, CT.

(Atlantic, April 1995): Background Concentrations of Inorganics in Soil. Installation Restoration Program, Naval Submarine Base - New London, Groton, Connecticut. Atlantic Environmental Services, Inc., Colchester, CT

(B&R Environmental, March 1997): Phase II Remedial Investigation for Naval Submarine Base, New London, Groton, Connecticut. Brown & Root Environmental, King of Prussia, PA.

(B&R Environmental, February 1998): Groundwater Monitoring Plan for Defense Reutilization and Marketing Office, Naval Submarine Base, New London, Groton, Connecticut. Brown & Root Environmental, King of Prussia, PA.

(CT, 1995): "Standards for Quality of Public Drinking Water." Title 19, Regulation 19-13, Section 19-13-B102. State of Connecticut

(CTDEP, December 1995): "Remediation Standard Regulations.". State of Connecticut Department of Environmental Protection, Bureau of Water Management, Permitting, Enforcement and Remediation Division, Hartford, Connecticut.

(NFESC, February 1996): Navy Installation Restoration Laboratory Quality Assurance Guide (Interim Guidance). Naval Facilities Engineering Service Center.

(OHM, September 1995): Final Report for Interim Remedial Action, Site 6, Naval Submarine Base, New London, Groton, Connecticut. OHM Remediation Services Corporation, Hopkinton, MA

(SCS, 1983): Soil Survey of New London County Connecticut. Soil Conservation Service.

(USGS, 1960): Geologic Map of the Uncasville Quadrangle, Connecticut, Surficial Geology. United States Geological Survey.

(USGS, 1967): Bedrock Geologic Map of the Uncasville Quadrangle, New London County, Connecticut. United States Geological Survey.

APPENDIX A

FIELD ACTIVITIES LOG BOOK

TITLE NSB-NLON

PROJECT NO. 7363

BOOK 2415

Monday 1/17/00

Work continued from Page

WEATHER: Clear, windy 4-15°F.

0710 SN arrives at PGH Airport - meets up w/ Keith Simpson (KS).

0805 SN + KS depart for NSB-NLON on flight #1430 to Providence, RI

1230 Arrive on site at NSB-NLON. SN and KS unpack equipment.

1400 KS + SN depart for water levels at Area A (see Logbook #1244).

1705 Arrive at building 166 after Area A water levels. Begin calibration of equipment, bottle prep, and equipment prep for Demo sampling on 1/18/00.

1900 KS + SN depart site for hotel.

~~SN
VOLD 1/17/00~~

Work continued to Page

SIGNATURE

Scott N. Reid

DATE

1/17/00

WITNESS

TITLE NSB-NLON

PROJECT NO. 7363

BOOK 2415

Tuesday 1/18/00

Work continued from Page

WEATHER (Am): Clear and cold, 2-10°F.

0645 SN + KS arrive at guard gate to get passes.

0705 SN + KS arrive at Bldg 166 and begin loading equipment into vehicles for site work. ~~SN~~ ~~KS~~ and sampling at Demo.

0730 Darlene arrives at Bldg 166 - KS and SN brief her of the activities for the shift.

0740 KS + SN depart for Demo.

0747 KS + SN arrive at non-tidal wells BMW6S + BMW6D.

0807 SN begins purging BMW6S. Did ~~read~~ ~~reading~~ ~~reading~~ = 0.0, static H₂O level = 9.75 Ft, casing volume = 1.4 gallons. Refer to Low Flow Purge Data Sheet for BMW6S for specific purge data.

0812 KS begins purging BMW6D. Refer to ~~data~~ ~~data~~ ~~data~~.

Work continued to Page

SIGNATURE

Scott N. Reid

DATE

1/18/00

WITNESS

DATE

TITLE NSB-NLON

PROJECT NO. 7363

Tues 1/18/00

BOOK 2415

Work continued from Page

to the Low Flow Purge Data Sheet for well BMW6D for specific purge data.

0905 SN begins sampling BMW6S - Sample ID DEMO-BMW6S-GW-07. Refer to GW Sample Log sheet for this well/sample for specific sampling data.

0915 KS begins sampling BMW6D - Sample ID DEMO-BMW6D-GW-07. Refer to GW Sample Log Sheet for this well/sample for specific sampling data.

0935 SN ends sampling and loads equip. in vehicle.

0943 KS ends sampling. SN + KS load vehicle with equipment and depart for BLDG 166.

1000 KS + SN arrive at BLDG 166. KS departs to pick up IDW drums. SN preps equipment and sample bottles for DEMO sampling.

Work continued to Page 179

SIGNATURE

178

WITNESS

DATE

1/18/00

DATE

TITLE NSB-NLON

PROJECT NO. 7363

Tues 1/18/00

BOOK 2415

Work continued from Page 178

1030 KS returns to BLDG 166

1045 KS + SN depart for LUNCH.

1125 KS + SN arrive at DEMO. Dump purge water into 55-gallon drum and proceed to wells BMW10D and 10S.

1155 KS sets up on well BMW10D; SN sets up on well BMW10S.

1210 KS begins purging of well BMW10D. Refer to the Low Flow Purge Data Sheet for well # BMW10D for specific purge data.

1220 SN begins purging well BMW10S. Refer to the L.F. Purge Data Sheet for well # BMW10S for specific purge data.

1315 KS begins sampling. Sample ID is DEMO-BMW10D-GW-07. This well has an MS/MSD associated with it. (cont)

Work continued to Page 180

SIGNATURE

WITNESS

DATE

01/18/00

DATE

179

TITLE NSB-NLON

PROJECT NO. 7363

BOOK 2415

Work continued from Page 179

Refer to the GW Sample Log Form associated with sample DEMO - BMW100-GW-07 for specific sampling info.

1315 SN begins sampling. Sample ID is DEMO - BMW105 - GW-07. Refer to the GW sample log sheet for this sample for specific sampling info.

1350 SN ends sampling. Preps for Low Tide water levels.

1355 SN begins Low ~~Flow~~ Tide water levels.

1415 SN arrives back at well BMW100-KS continues Low Tide water levels. SN finishes sampling BMW105. Loads equipment in vehicle.

1422 KS ends Low Tide water levels. Cap wells BMW105 and 100. Proceed to dump purge water into EDW drum. Depart DEMO.

1450 KS & SN arrive at BLD 106, unload vehicles

Work continued to Page 181

SIGNATURE

Scott. Reid

WITNESS

DATE

1/18/00

DATE

180

TITLE NSB-NLON

PROJECT NO. 7363

BOOK 2415

Work continued from Page 180

SAMPLE SUMMARY (ROUND 7)

WELL #	DATE SAMPLED	TIME	COMMENTS
BMW15	1-21-00	1525	
BMW25	1-20-00	1500	
BMW20	1-20-00	1510	
BMW65	1/18/00	0905	
BMW60	1/18/00	0915	
BMW95	1-19-00	0840	
BMW105	1/18/00	1315	
BMW100	1/18/00	1315	
BMW115	1-19-00	1415	
BMW100	1-19-00	1433	

DUP
BLACK SULPHUR FINE
SULPHUR OIL
MS/MSD

Work continued to Page

SIGNATURE

Scott. Reid

WITNESS

DATE

1/18/00

DATE

181

TITLE NSB-NLON

PROJECT NO. 7363

BOOK 2415

Work continued from Page 180

WEATHER (PM): Windy, COLO, 15-22°F

1650

KS & SM to Walmart for supplies,
then to hotel.

Sun

7/18/00

Work continued to Page

SIGNATURE

Scott. New

182

WITNESS

DATE

11/18/00

DATE

TITLE NSB-NUN

PROJECT NO. 7365

BOOK 2415

WED. 1.19.00

Work continued from Page

WEATHER: CLOUD, CLEAR 3-22°F

0650

KS & SN @ BLD 166 CAL & LOAD
EQUIPMENT. SCOTT WORKING ON
AREA A. KS ON NW 9 @ DRMO

0918

COMPLETE PURGE & SAMPLING @
6MW9S ALSO COLLECTED DUP @
THIS WELL GUPD 011900

0935

LOAD TRUCK TO BLD 166
PAPER WORK & PREP FOR GW SAMPLING
TO AREA A HELP SCOTT WITH
PURGING THEN LUNCH

1200

RETURN TO BLD 166 LOAD SUV'S
FOR SAMPLING @ DRMO

1235

TO DRMO & SET-UP ON IIS & D
COMPLETE PURGING & SAMPLING, LOAD

1500

SUV'S TO BLD 166. CLEAN EQUIP.
PAPER WORK PREP FOR HIGH TIDE
WATER LEVELS & SAMPLING AT AREA ASEE ALSO LOG BOOK
FOR AREA A

SIGNATURE

K. S. Simi

WITNESS

Work continued to Page

DATE

1.19.00

DATE

183

TITLE NSB NCD NWH

PROJECT NO. 7363

THUR. 1-20-00

BOOK 2415

Work continued from Page

WEATHER: SNOW, CLOUD 8-21°F
 0650 SCOTT NEIL & KEITH SIMPSON
 @ BLD 166 PREP FOR HIGH TIDE
 WL THEN SAMPLING @ AREA A
 0805 TO DRMO COMPLETE HIGH TIDE
 WL @ 0835 RETURN TO
 BLD 166, LOAD SUV'S FOR
 AREA A
 1348 KS & SN TO DRMO SET-UP ON
 25' D COMPLETE PURGE &
 SAMPLING OF 6MW/25' D
 1535 RETURN TO BLD 166 UNLOAD
 SUV'S PAPER WORK & PREP FOR
 1-21-00 SAMPLING @ AREA A

Work continued to Page

SIGNATURE

184

WITNESS

DATE

1-20-99

DATE

TITLE NSB NCD IX

PROJECT NO. 7363

FRIDAY 1-21-00

BOOK 2415

Work continued from Page

WEATHER: COLD, WINDY 5-20°F
 LITE SNOW THUR. PM
 1310 TO DRMO K. SIMPSON, SCOTT IS
 WORKING AT AREA A.
 SET-UP TO PURGE & SAMPLE @
 6MW/15. "LAST" WELL.
 1600 COMPLETE SAMPLING @ DRMO
 10 WELLS SAMPLED ALL PURGE
 WATER WAS DUMPED INTO A DRUM
 LABELED & SUPPLIED BY THE BASE
 THEY WILL REMOVE DRUM FROM
 DRMO NEXT WEEK
 1635 NITROGEN CYL. RETURNED TO
 BOC GASES.
 WILL CLEAN/PACK & RETURN RENTED
 EQUIPMENT THIS WEEKEND

END ROUND
DRMO

7

Work continued to Page

SIGNATURE

WITNESS

DATE

1-21-00

DATE

185

APPENDIX B

TIDE TABLES

All times listed are in Local Time, and all heights are in Feet.

New London, Connecticut

Tide Predictions (High and Low Waters)
NOAA, National Ocean Service

December, 1999

Standard Time

Day	Time	Ht.	Time	Ht.	Time	Ht.	Time	Ht.
1 W	421am H	2.7	1038am L	0.3	443pm H	2.5	1057pm L	0.2
2 Th	519am H	2.8	1137am L	0.2	544pm H	2.4	1148pm L	0.2
3 F	609am H	2.9	1229pm L	0.2	635pm H	2.3		
4 Sa	1234am L	0.2	652am H	2.9	117pm L	0.1	718pm H	2.3
5 Su	118am L	0.2	730am H	3.0	200pm L	0.1	757pm H	2.3
6 M	159am L	0.3	806am H	3.0	241pm L	0.0	834pm H	2.3
7 Tu	240am L	0.3	841am H	3.0	322pm L	0.0	911pm H	2.3
8 W	320am L	0.3	916am H	3.0	402pm L	0.0	948pm H	2.3
9 Th	402am L	0.4	952am H	3.0	444pm L	0.0	1028pm H	2.3
10 F	445am L	0.5	1029am H	2.9	527pm L	0.1	1109pm H	2.3
11 Sa	530am L	0.6	1107am H	2.8	611pm L	0.1	1153pm H	2.3
12 Su	618am L	0.6	1149am H	2.7	658pm L	0.2		
13 M	1240am H	2.2	710am L	0.7	1235pm H	2.6	746pm L	0.2
14 Tu	130am H	2.3	806am L	0.7	127pm H	2.5	835pm L	0.3
15 W	223am H	2.4	903am L	0.6	226pm H	2.4	925pm L	0.3
16 Th	317am H	2.5	1000am L	0.5	328pm H	2.3	1015pm L	0.2
17 F	410am H	2.7	1055am L	0.3	428pm H	2.3	1104pm L	0.1
18 Sa	502am H	2.9	1149am L	0.1	526pm H	2.4	1152pm L	0.0
19 Su	553am H	3.2	1240pm L	-0.2	622pm H	2.5		
20 M	1241am L	-0.1	643am H	3.4	131pm L	-0.4	715pm H	2.6
21 Tu	130am L	-0.2	733am H	3.6	221pm L	-0.6	808pm H	2.7
22 W	221am L	-0.3	824am H	3.7	311pm L	-0.7	900pm H	2.7
23 Th	313am L	-0.3	915am H	3.7	402pm L	-0.7	953pm H	2.8
24 F	406am L	-0.3	1008am H	3.6	454pm L	-0.7	1047pm H	2.7
25 Sa	502am L	-0.2	1102am H	3.4	547pm L	-0.5	1143pm H	2.7
26 Su	601am L	-0.1	1159am H	3.1	641pm L	-0.4		
27 M	1241am H	2.7	702am L	0.0	1258pm H	2.8	737pm L	-0.2
28 Tu	142am H	2.6	805am L	0.1	201pm H	2.6	833pm L	-0.1
29 W	245am H	2.6	909am L	0.2	306pm H	2.3	929pm L	0.1
30 Th	347am H	2.6	1011am L	0.2	410pm H	2.2	1023pm L	0.2
31 F	446am H	2.6	1109am L	0.2	511pm H	2.1	1115pm L	0.2

New London, Connecticut

Tide Predictions (High and Low Waters)
NOAA, National Ocean Service

January, 2000

Standard Time

Day	Time	Ht.	Time	Ht.	Time	Ht.	Time	Ht.
1 Sa	539am H	2.7	1205pm L	0.1	607pm H	2.0		
2 Su	1204am L	0.2	624am H	2.7	1253pm L	0.1	652pm H	2.0
3 M	1249am L	0.2	704am H	2.8	136pm L	0.0	732pm H	2.0
4 Tu	132am L	0.2	741am H	2.8	218pm L	0.0	810pm H	2.1
5 W	214am L	0.2	817am H	2.9	258pm L	-0.1	848pm H	2.1
6 Th	256am L	0.2	853am H	2.9	338pm L	-0.1	925pm H	2.2
7 F	337am L	0.2	929am H	2.9	418pm L	-0.2	1004pm H	2.2
8 Sa	419am L	0.3	1005am H	2.8	459pm L	-0.1	1043pm H	2.2
9 Su	503am L	0.3	1043am H	2.8	541pm L	-0.1	1123pm H	2.3
10 M	549am L	0.4	1124am H	2.7	624pm L	0.0		
11 Tu	1206am H	2.3	638am L	0.4	1207pm H	2.6	709pm L	0.0
12 W	1252am H	2.4	731am L	0.4	1256pm H	2.4	756pm L	0.1
13 Th	141am H	2.4	829am L	0.4	152pm H	2.3	845pm L	0.2
14 F	235am H	2.5	928am L	0.3	253pm H	2.2	937pm L	0.2
15 Sa	332am H	2.7	1027am L	0.1	358pm H	2.1	1030pm L	0.1
16 Su	430am H	2.9	1124am L	-0.1	501pm H	2.1	1124pm L	0.0
17 M	527am H	3.1	1220pm L	-0.3	601pm H	2.2		
18 Tu	1218am L	-0.1	623am H	3.3	643pm L	-0.4	659pm H	2.3
19 W	112am L	-0.2	718am H	3.4	704pm L	-0.6	753pm H	2.5
20 Th	205am L	-0.3	811am H	3.5	766pm L	-0.7	846pm H	2.6
21 F	259am L	-0.4	903am H	3.4	828pm L	-0.8	938pm H	2.7
22 Sa	353am L	-0.4	955am H	3.3	434pm L	-0.7	1030pm H	2.7
23 Su	447am L	-0.3	1047am H	3.1	524pm L	-0.5	1123pm H	2.7
24 M	543am L	-0.3	1140am H	2.9	615pm L	-0.4		
25 Tu	1216am H	2.7	640am L	-0.1	1235pm H	2.6	707pm L	-0.2
26 W	112am H	2.6	739am L	0.0	131pm H	2.4	800pm L	-0.1

APPENDIX C

GROUNDWATER LEVEL MEASUREMENT SHEET

[illegible]

* Measurements to the nearest 0.01 foot.

* MEASURED AT TOP OF STEEL RISER

ROUND 7



Tetra Tech NUS, Inc.

GROUNDWATER LEVEL MEASUREMENT SHEET

Project:	<u>NSB-NLON</u>	Site:	<u>DRMO</u>
Project No.:	<u>7363</u>	Personnel:	<u>SIMPSON / NEIL</u>
Temperature:	<u>13°F</u>	Date:	<u>118 09</u> ^{KS}
Precipitation:	<u>NONE</u>	Level Indicator Type:	<u>HERON</u>
Tide:	<u>LOW @ 1338</u>	Serial Number:	<u>NUS 001</u>

Well/Piezometer Number	Time	(A) Elevation of Reference Point (feet)*	(B) Water Level Indicator Reading (feet)*	=(A)-(B) Groundwater Elevation (feet)*	Total Well Depth (feet)*	Tidally Influenced	Comments
6MW1S	1411	8.63	7.20	1.43	15.68	Y	
6MW2S	1404	7.30	5.83	1.47	13.63	Y	
6MW2D	1406	7.85	5.44	2.41	88.84	Y	
6MW6S	1420	12.16	8.79	3.37	18.58	N	
6MW6D	1419	12.50	9.11	3.39	46.00	N	6" OPEN BOREHOLE *
6MW9S	1416	7.52	4.30	3.22	11.75	N	
6MW10S	1414	5.19	3.58	1.61	13.31	Y	
6MW10D	1422	5.01	2.17	2.84	54.06	Y	
6MW11S	1355	4.92	3.36	1.56	13.50	Y	
6MW11D	1357	5.31	2.60	2.71	85.00	Y	
SG-1	1409	5.67	4.31	1.36	--	Y	River Gauge

* Measurements to the nearest 0.01 foot.

* MEASURED AT TOP OF STEEL RISER

APPENDIX D

MONITORING INSTRUMENT CALIBRATION LOG



PROJECT NAME: NSB-N10N AREA-A/DRMO

PROJECT NUMBER : 5082/7363

Instrument Rented From: US ENVIRONMENTAL



PROJECT NAME: NSB-NUN AREA-A/DRMO

PROJECT NUMBER: 5082/7363

[illegible]




PROJECT NAME: NSB-NLOW (DRMO and Arzet A)

PROJECT NUMBER: 7363/CTD 267
5082/CTD 203

[illegible]

APPENDIX E

**GROUNDWATER SAMPLE LOGSHEETS AND
LOW-FLOW PURGE DATA SHEETS**

Page 1 of 2

☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

Date: 1-21-00	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: 1525	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	CLEAR	6.49	10.98	6.1	0	0	100	5.99

Date:	1-21-00
Method:	Low Flow/Bladder Pump
Monitor Reading (ppm):	0
Well Casing Diameter & Material	
Type:	2 PVC
Total Well Depth (TD):	15.7
Static Water Level (WL):	6.79
One Casing Volume(gal):	1.5
Start Purge (hrs):	1402
End Purge (hrs):	1522
Total Purge Time (min):	80
Total Vol. Purged (gal):	5.2

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	40 ml Vial	3
TCL SEMIVOLATILES	4° C	Qt. Amber Glass	2
TCL PEST/PCBs	4° C	Qt. Amber Glass	2
TCL PAH	4° C	Qt. Amber Glass	2
TAL METALS (TOTAL)	HNO ₃ / 4° C	L PE	1
TAL METALS (DISSOLVED) KES	HNO ₃ / 4° C	L PE	

1. *Journal of the American Medical Association*, 1997; 277: 1033-1038.

MS/MSD

Duplicate ID No.:

W. J. S. h.

[illegible]

Water Quality Meter (S/N): YSI

Notes:

Control Box Type (S/N): QED

Turbidimeter (S/N): LA MOTTE



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2

Project Site Name: NSB-NLON / DRMO
 Project No.: 7363

Sample ID No.: DRMO- 6MW25 GW-07
 Sample Location: 6MW25
 Sampled By: S. NIEL
 C.O.C. No.: 011900 07
 Type of Sample:
☒ Low Concentration
☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date: <u>1-20-00</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: <u>1500</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	<u>CLEAR</u>	<u>7.06</u>	<u>23.98</u>	<u>7.5</u>	<u>3.8</u>	<u>3.24</u>	<u>-132</u>	<u>14.45</u>

PURGE DATA:

Date: 1-20-00
 Method: Low Flow/Bladder Pump
 Monitor Reading (ppm): —
 Well Casing Diameter & Material
 Type: 2 PVC
 Total Well Depth (TD): 13.60
 Static Water Level (WL): 1.90'
 One Casing Volume(gal): 1.1
 Start Purge (hrs): 1407
 End Purge (hrs): 1457
 Total Purge Time (min): 50
 Total Vol. Purged (gal): 4.9

See Attached Low Flow Purge Data Sheet
 for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4°C	40 ml Vial	<u>3</u>
TCL SEMIVOLATILES	4°C	Qt. Amber Glass	<u>2</u>
TCL PEST/PCBs	4°C	Qt. Amber Glass	<u>2</u>
TCL PAH	4°C	Qt. Amber Glass	<u>2</u>
TAL METALS (TOTAL)	HNO ₃ / 4°C	L PE	<u>1</u>
TAL METALS (DISSOLVED)	HNO ₃ / 4°C	L PE	<u>1</u> (SW)

OBSERVATIONS / NOTES:

FINAL H₂O LEVEL = 7.19 FT.
 END SAMPLING @ 1518

Circle if Applicable:

MS/MSD

Duplicate ID No.: _____

Signature(s):



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW25

PROJECT: <u>NSB-NLON, DRMO</u>		DATE: <u>1-20-00</u>	
PROJECT NUMBER: <u>7363</u>		WEATHER: <u>Cloudy, Windy, Low 20's.</u>	
SITE: <u>DRMO</u>		PERSONNEL: <u>SCOTT NEIL</u>	

Well Screen Depth: <u>3.6 / 13.6</u> ft.	Pump Type/Material: <u>BLADDER/PVC</u>	Tide Cycle: <input type="checkbox"/> High @ _____
Initial Water Level: <u>6.90</u> @ <u>1407</u> hrs.	Pump Intake Depth: <u>10.0</u> TPVC	<input checked="" type="checkbox"/> Low @ <u>1520</u>
Total Purge Volume= <u>4.9</u> (gal/L)	Total Purge Time= <u>50</u> (min)	<input type="checkbox"/> Not Affected

Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
1407	6.90	—	—	30R/30D 15 PSI	—	—	—	—	—	—	—	BEGIN Purging
1412	6.96	355	355		7.4	7.20	23.73	4.05	10.3	14.29	-147	SUSPENDED BLK
1417	6.96				7.5	7.14	23.87	3.30	3.6	14.38	-146	Fines.
1422	6.98				7.4	7.10	23.93	3.49	5.6	14.42	-145	
1427	7.02				7.4	7.11	23.92	2.94	5.1	14.44	-143	
1432	7.04				7.5	7.10	23.96	3.21	5.1	14.44	-141	
1437	7.05				7.5	7.09	23.97	3.21	3.9	14.44	-139	
1442	7.06				7.5	7.08	23.99	3.19	3.8	14.46	-137	
1447	7.08				7.5	7.08	23.99	3.45	3.4	14.48	-135	
1452	7.10				7.4	7.08	24.02	3.26	4.2	14.47	-133	
1457	7.11				7.5	7.06	23.98	3.24	3.8	14.45	-132	END Purging
BEGIN ^W SAMPLING @ 1500. Sample #1 DRMO-6MW25-6W-07.												
END SAMPLING @ 1518.												

Water Quality Meter (S/N): YSI (1939332)Control Box Type (S/N): QED (15800)Turbidimeter (S/N): LA MOTTE (0639-1298)

Notes: _____



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2

Project Site Name: NSB-NLON / DRMO
 Project No.: 7363

Sample ID No.: DRMO- 6MW/2D GW-07Sample Location: 6MW/2DSampled By: R. SIMPSONC.O.C. No.: 011900-07

Type of Sample:

☒ Low Concentration☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
<u>1-20-00</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Time: <u>1510</u>	<u>CLEAR</u>	<u>6.90</u>	<u>33.75</u>	<u>9.8</u>	<u>8.3</u>	<u>0</u>	<u>-308</u>	<u>21.17</u>
Method: Low Flow/Bladder Pump								

PURGE DATA:

Date: 1-20-00
 Method: Low Flow/Bladder Pump
 Monitor Reading (ppm): 0
 Well Casing Diameter & Material
 Type: 2 PVC
 Total Well Depth (TD): 78.3
 Static Water Level (WL): 5.61
 One Casing Volume(gal): 11.9
 Start Purge (hrs): 1411
 End Purge (hrs): 1507
 Total Purge Time (min): 56
 Total Vol. Purged (gal): 4.5

See Attached Low Flow Purge Data Sheet
 for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	40 ml Vial	<u>3</u>
TCL SEMIVOLATILES	4° C	Qt. Amber Glass	<u>2</u>
TCL PEST/PCBs	4° C	Qt. Amber Glass	<u>2</u>
TCL PAH	4° C	Qt. Amber Glass	<u>2</u>
TAL METALS (TOTAL)	HNO ₃ / 4° C	L PE	<u>1</u>
TAL METALS (DISSOLVED) <u>KES</u>	HNO₃ / 4° C	L PE	<u>—</u>

OBSERVATIONS / NOTES:

DISCHARGE LINE FRZ. USED WARM WATER TO THAW. ON
 TOP 3' OF TUBING OUT OF WELL

Circle if Applicable:

MS/MSD

Duplicate ID No.:

Signature(s):



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW2D

PROJECT: <u>NSB-NLON, DRMD</u>		DATE: <u>1-20-00</u>	
PROJECT NUMBER: <u>7363</u>		WEATHER: <u>COLD WINDY 20°F OVERCAST</u>	
SITE: <u>DRMU</u>		PERSONNEL: <u>R. SIMPSON</u>	

Well Screen Depth: <u>68.8 / 78.8</u> ft.	Pump Type/Material: <u>BLADDER/PVC</u>	Tide Cycle: <input type="checkbox"/> High @
Initial Water Level: <u>5.61</u> @ <u>1400</u> hrs.	Pump Intake Depth: <u>73.0</u> TAC	<input checked="" type="checkbox"/> Low @ <u>1520</u>
Total Purge Volume = <u>4.5</u> (gal/L)	Total Purge Time = <u>56</u> (min)	<input type="checkbox"/> Not Affected

Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
1415	6.13	0	270	40L/40D	9.6	6.88	33.49	0	16	20.84	-203	
1425	6.15	↓	305	50 PSI	9.6	6.82	32.94	0	12	20.71	-250	
1430	6.20	↓		35R/35D	9.5	6.82	33.41	0	10	20.77	-270	
1440	6.28	↓		50 PSI	9.8	6.87	33.62	0	8.6	21.27	-301	
1445	6.14	↓			9.6	6.88	34.19	0	8.5	21.34	-306	
1450	6.03	↓			9.7	6.88	33.67	0	8.5	21.00	-309	
1455	6.18	↓			9.8	6.90	34.00	0	8.4	21.32	-307	
1500	6.14	↓			9.8	6.90	33.81	0	8.3	21.29	-307	
1505	6.10	1780	↓	↓	9.8	6.90	33.75	0	8.3	21.17	-308	END PURGE

Water Quality Meter (S/N): YS

Notes: _____

Control Box Type (S/N): QEDTurbidimeter (S/N): LA MOTTE



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2Project Site Name: NSB-NLON / DRMO
Project No.: 7363Sample ID No.: DRMO- 6MW6S GW-07Sample Location: 6MW6SSampled By: S. NIELC.O.C. No.: 011800-07

Type of Sample:

☒ Low Concentration☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date: <u>1-18-00</u>	Color	<u>6.0</u> pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: <u>0905</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	<u>CLEAR</u>	<u>9.6</u>	<u>0.252</u>	<u>9.6</u>	<u>0.3</u>	<u>7.23</u>	<u>242</u>	<u>0.12</u>

PURGE DATA:

Date: 1-18-00

Method: Low Flow/Bladder Pump

Monitor Reading (ppm): 0.0

Well Casing Diameter & Material

Type: 2 PVCTotal Well Depth (TD): 18.58Static Water Level (WL): 9.75One Casing Volume(gal): 1.4Start Purge (hrs): 0807End Purge (hrs): 0902Total Purge Time (min): 55Total Vol. Purged (gal): 3.4See Attached Low Flow Purge Data Sheet
for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	<u>(3)</u> 40 ml Vial	✓
TCL SEMIVOLATILES	4° C	<u>(2)</u> Qt. Amber Glass	✓
TCL PEST/PCBs	4° C	<u>(2)</u> Qt. Amber Glass	✓
TCL PAH	4° C	<u>(2)</u> Qt. Amber Glass	✓
TAL METALS (TOTAL)	HNO ₃ / 4° C	<u>(1)</u> L PE	✓
TAL METALS (DISSOLVED)	HNO ₃ / 4° C	L PE	✓ <u>(5N)</u>

OBSERVATIONS / NOTES:

Circle if Applicable:

MS/MSD

Duplicate ID No.:

Signature(s):

Scott W. Niel



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW6S

PROJECT: NSB-NLON, DRMD
 PROJECT NUMBER: 7363
 SITE: DRMU

DATE: 1-18-00
 WEATHER: Breezy, clear, cold, 3-7°F
 PERSONNEL: Scott Neil

Well Screen Depth: 8.6 / 118.6 ft.
 Initial Water Level: 9.75 @ 0807 hrs.

Pump Type/Material: BLADDER/ PVC
 Pump Intake Depth: 14.0 TPC

Tide Cycle: ☐ High @ _____
☐ Low @ _____
☒ Not Affected

Total Purge Volume= 3.4 (gal) / L

Total Purge Time= 55 (min)

Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
0807	9.75	—	—	454/450	—	—	—	—	—	—	—	Begin Purging
0812	9.73	350	233		9.6	6.18	0.253	6.97	6.6	0.12	234	1145
0817	9.71				9.6	6.18	0.253	7.62	4.0	0.12	234	2330
0822	9.71				9.7	6.10	0.253	7.68	3.0	0.12	236	3445
0827	9.71				9.6	6.12	0.252	7.60	1.8	0.12	236	4660
0832	9.71				9.4	6.07	0.254	7.30	1.4	0.12	242	
0837	9.70				9.7	6.13	0.252	7.40	1.2	0.12	239	
0842	9.70				9.7	6.12	0.253	6.90	0.8	0.12	239	
0847	9.70				9.6	6.11	0.252	7.37	0.6	0.12	240	
0852	9.69				9.6	6.12	0.253	6.91	0.5	0.12	241	
0857	9.69				9.6	6.11	0.252	7.18	0.3	0.12	242	
0902	9.69	✓	✓	✓	9.6	6.10	0.252	7.23	0.3	0.12	242	End purging
		Begin sampling @ 0905 - Sample # DRMD-6MW6S-GW-07										
		End at sampling @ 0935.										

Water Quality Meter (S/N): YSI

Notes: _____

Control Box Type (S/N): QED

Turbidimeter (S/N): La MOTTE (0639-1298)



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2

Project Site Name: NSB-NLON / DRMO
 Project No.: 7363

Sample ID No.: DRMO- 6MW6D GW-07
 Sample Location: 6MW6D
 Sampled By: RES
 C.O.C. No.: 011800-07
 Type of Sample:
☒ Low Concentration
☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date: <u>1-15-00</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: <u>0915</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	<u>CLEAR</u>	<u>5.95</u>	<u>3.732</u>	<u>8.9</u>	<u>19</u>	<u>1.33</u>	<u>89</u>	<u>1.97</u>

PURGE DATA:

Date: 1-15-00
 Method: Low Flow/Bladder Pump
 Monitor Reading (ppm): 0
 Well Casing Diameter & Material
 Type: 6" K5 OPEN BORE HOLE
 Total Well Depth (TD): 46.0'
 Static Water Level (WL): 9.04
 One Casing Volume (gal): 54.3
 Start Purge (hrs): 0912
 End Purge (hrs): 0912
 Total Purge Time (min): 60
 Total Vol. Purged (gal): 4.8

See Attached Low Flow Purge Data Sheet
 for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	40 ml Vial	✓
TCL SEMIVOLATILES	4° C	Qt. Amber Glass	✓
TCL PEST/PCBs	4° C	Qt. Amber Glass	✓
TCL PAH	4° C	Qt. Amber Glass	✓
TAL METALS (TOTAL)	HNO ₃ / 4° C	L PE	✓
TAL METALS (DISSOLVED) K5	HNO ₃ / 4° C	L PE	✓

OBSERVATIONS / NOTES:

6" WELL; OPEN BORE HOLE

1.47 GAL/FT

Circle if Applicable:

MS/MSD

Duplicate ID No.:

Signature(s):

RES



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: GMW 60

PROJECT: NSB-NLON, DRMO
 PROJECT NUMBER: 7363
 SITE: DRMO

DATE: 1-18-00
 WEATHER: COLD, CLEAR -3°F
 PERSONNEL: _____

Well Screen Depth: 30.5 / 46.0 ft.
 Initial Water Level: 9.04 @ 0.005 hrs.

Pump Type/Material: BLANXER/PVC
 Pump Intake Depth: _____

Tide Cycle: ☐ High @ _____
☐ Low @ _____
☒ Not Affected

Total Purge Volume= 4.8 (gal/4)Total Purge Time= 60 (min)

Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
0815	9.09	0	360	20 PSI / 25 PSI	8.2	6.28	3.729	1.01	85	1.99	130.1	
0820	9.06		300		8.3	5.93	3.736	1.10	60	2.00	106	
0830	9.04				8.5	5.97	3.750	9.67	45	2.00	100	
0835	9.04				8.5	5.97	3.763	7.40	45	2.00	97	
0840	9.03				8.6	5.95	3.772	3.31	45	1.99	95	
0845	9.04				9.0	5.96	3.774	2.43	45	1.99	94	
0850	9.04				8.9	5.96	3.752	1.01	45	1.97	94	
0855	9.04				9.1	5.96	3.731	1.80	39	1.99	92	
0900	9.04				9.0	5.96	3.720	1.57	39	1.99	91	
0905	9.04				8.9	5.95	3.731	1.44	23	1.98	90	
0910	9.04	18,000			8.9	5.95	3.732	1.33	19	1.97	89	END PURGE

Water Quality Meter (S/N): YSINotes: COLDControl Box Type (S/N): GEDTurbidimeter (S/N): LA MOTTE



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2

Project Site Name: NSB-NLON / DRMO
 Project No.: 7363

Sample ID No.: DRMO- 6MW9S GW-07
 Sample Location: 6MW9S
 Sampled By: K. SIMPSON
 C.O.C. No.: 011900
 Type of Sample:
☒ Low Concentration
☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date: <u>1-19-00</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: <u>0940</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	<u>CLEAR</u>	<u>5.10</u>	<u>0.049</u>	<u>9.6</u>	<u>0.2</u>	<u>0.63</u>	<u>282</u>	<u>0.02</u>

PURGE DATA:

Date: 1-19-00
 Method: Low Flow/Bladder Pump
 Monitor Reading (ppm): _____
 Well Casing Diameter & Material
 Type: 2 PVC
 Total Well Depth (TD): 11.8
 Static Water Level (WL): 3.58
 One Casing Volume (gal): 1.4
 Start Purge (hrs): 0945
 End Purge (hrs): 0935
 Total Purge Time (min): 50
 Total Vol. Purged (gal): 4.3

See Attached Low Flow Purge Data Sheet
 for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4°C	40 ml Vial	<u>6</u>
TCL SEMIVOLATILES	4°C	Qt. Amber Glass	<u>4</u>
TCL PEST/PCBs	4°C	Qt. Amber Glass	<u>4</u>
TCL PAH	4°C	Qt. Amber Glass	<u>4</u>
TAL METALS (TOTAL)	HNO ₃ / 4°C	L PE	<u>2</u>
TAL METALS (DISSOLVED) — <u>RES</u>	HNO ₃ / 4°C	<u>L PE</u>	<u>—</u>
		<u>2X VOL COLLECTED</u>	
		<u>FOR DUF</u>	

OBSERVATIONS / NOTES:

COLD 10°F

Circle if Applicable:

MS/MSD

Duplicate ID No.:

GWFD-011900

Signature(s):

K. Simpson

Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW95

[illegible]

Water Quality Meter (S/N): YS1

Notes:

Control Box Type (S/N): QED

Turbidimeter (S/N): La MOTTE



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2

Project Site Name: NSB-NLON / DRMO
 Project No.: 7363

Sample ID No.: DRMO- 6MW10S GW-07
 Sample Location: 6MW10S
 Sampled By: S. NEIL
 C.O.C. No.: 011800-7
 Type of Sample:
☒ Low Concentration
☐ High Concentration

- ☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type: _____
☐ QA Sample Type: _____

SAMPLING DATA:

Date:	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
<u>1-18-00</u>	<u>Visual</u>	<u>Standard</u>	<u>mS/cm</u>	<u>Degrees C</u>	<u>NTU</u>	<u>mg/l</u>	<u>mV</u>	<u>ppt</u>
Time: <u>7:50 1315</u>	<u>Clear</u>	<u>7.33</u>	<u>11.18</u>	<u>10.9</u>	<u>0.1</u>	<u>0.47</u>	<u>-264</u>	<u>6.34</u>
Method: Low Flow/Bladder Pump								

PURGE DATA:

Date: 1-18-00
 Method: Low Flow/Bladder Pump
 Monitor Reading (ppm): 0.0
 Well Casing Diameter & Material
 Type: 2 PVC
 Total Well Depth (TD): 13.30
 Static Water Level (WL): 9.50 3.59
 One Casing Volume (gal): 1.6
 Start Purge (hrs): 1220
 End Purge (hrs): 1310
 Total Purge Time (min): 50
 Total Vol. Purged (gal): 3.6

See Attached Low Flow Purge Data Sheet
 for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	40 ml Vial	
TCL SEMIVOLATILES	4° C	Qt. Amber Glass	
TCL PEST/PCBs	4° C	Qt. Amber Glass	
TCL PAH	4° C	Qt. Amber Glass	
TAL METALS (TOTAL)	HNO ₃ / 4° C	L PE	
TAL METALS (DISSOLVED)	HNO ₃ / 4° C	L PE	

OBSERVATIONS/NOTES:

Suspended solids (Black) in sample.
 Sulphur odor.
 Final H₂O level = 4.03 Ft.

Circle if Applicable:

MS/MSD

Duplicate ID No.:

Signature(s):



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW10S

PROJECT: <u>NSB-NLON, DRMO</u>					DATE: <u>1-18-00</u>							
PROJECT NUMBER: <u>7363</u>					WEATHER: <u>Sunny, clear, windy, cold, 11-16°F</u>							
SITE: <u>DRMU</u>					PERSONNEL: <u>SCOTT NEIL</u>							
Well Screen Depth: <u>3.3</u> / <u>13.3</u> ft.					Pump Type/Material: <u>BUNDER/PVC</u>					Tide Cycle: <input type="checkbox"/> High @ _____ <input checked="" type="checkbox"/> Low @ _____ <input type="checkbox"/> Not Affected		
Initial Water Level: <u>3.59'</u> @ <u>1220</u> hrs.					Pump Intake Depth: <u>9.0</u> T <u>PVC</u>							
Total Purge Volume= _____ (gal/L)					Total Purge Time= _____ (min)							
Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
1220	3.59	—	—	30R/30D 15 PSI	—	—	—	—	—	—	—	Begin Purging
1225	3.70	355	355	40R/40D 15 PSI	10.8	7.28	10.44	0.45	2.9	5.92	-70	Suspended Black particles
1230	3.74	215	266		10.8	7.32	10.47	0.41	1.5	6.00	-161	LGT SULFUR OXID.
1235	3.75				10.8	7.35	10.57	0.52	1.9	6.00	-187	
1240	3.77				10.8	7.35	10.76	0.48	0.8	6.11	-208	
1245	3.77				10.8	7.35	10.77	0.58	0.6	6.12	-221	
1250	3.78				10.8	7.35	10.88	0.65	0.4	6.16	-231	
1255	3.79				10.8	7.34	10.96	0.41	0.5	6.22	-239	
1300	3.79				10.8	7.34	11.10	0.43	0.3	6.25	-248	
1305	3.79				10.9	7.33	11.14	0.45	0.3	6.29	-257	
1310	3.81	↓	↓	↓	10.9	7.33	11.18	0.47	0.1	6.34	-264	End Purging
Begin sampling @ 1315 - sample ID DRMO - 6MW10S - GM-07.												
End sampling @ 1350												

Water Quality Meter (S/N): YSI (193933R)

Notes: _____

Control Box Type (S/N): QEDTurbidimeter (S/N): LA MOTTE (0639-1298)



Page 1 of 2

Sample ID No.: DRMO- 6MW/10D GW-07
Sample Location: 6MW/10D
Sampled By: RES
C.O.C. No.: 011800-07
Type of Sample:
☒ Low Concentration
☐ High Concentration

☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type:
☐ QA Sample Type:

Date: 1-18-00	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: 1315	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	CLEAR	7.25	18.42	12.4	0.6	3.31	-142	11.22

Date:	1-10-00
Method:	Low Flow/Bladder Pump
Monitor Reading (ppm):	
Well Casing Diameter & Material	
Type:	2 PVC
Total Well Depth (TD):	54.10
Static Water Level (WL):	2.53
One Casing Volume (gal):	8.4
Start Purge (hrs):	1210
End Purge (hrs):	1310
Total Purge Time (min):	60
Total Vol. Purged (gal):	4.8

**See Attached Low Flow Purge Data Sheet
for Purge Data**

[illegible]

F14SH MT

MSMSD

Duplicate ID No.:

Signature(s):

K-15 Simp

[illegible]

Water Quality Meter (S/N): YSI

Control Box Type (S/N): QED

Turbidimeter (S/N): LA MOTTE

Notes: MS/MSD COLLECTED



Page 1 of 2

Sample ID No.: DRMO- 6MW11S GW-07
Sample Location: 6MW11S
Sampled By: KEITH SIMPSON
C.O.C. No.: 011900-07
Type of Sample:
☒ Low Concentration
☐ High Concentration

☐ Domestic Well Data
☒ Monitoring Well Data
☐ Other Well Type:
☐ QA Sample Type:

Date: 1-19-00	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: 1415	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: Low Flow/Bladder Pump	CLEAR	7.49	12.31	9.9	1.6	5.77	-326	7.06

Date:	1-19-00
Method:	Low Flow/Bladder Pump
Monitor Reading (ppm):	
Well Casing Diameter & Material	
Type:	2 PVC
Total Well Depth (TD):	13.50
Static Water Level (WL):	3.24
One Casing Volume (gal):	1.7
Start Purge (hrs):	1320
End Purge (hrs):	1410
Total Purge Time (min):	50
Total Vol. Purged (gal):	3.2

See Attached Low Flow Purge Data Sheet
for Purge Data

[illegible]

MS/MSD

Signature(s):

7/1-1 Sp.

[illegible]

Water Quality Meter (S/N): YS1

Notes:

Control Box Type (S/N): QED

Turbidimeter (S/N): LA NUTTE



Tetra Tech NUS, Inc.

GROUNDWATER SAMPLE LOG SHEET

Page 1 of 2Project Site Name: NSB-NLON / DRMOProject No.: 7363Sample ID No.: DRMO- 6MW11D GW-07Sample Location: 6MW11DSampled By: S. NEILC.O.C. No.: 011900-07☐ Domestic Well Data☒ Monitoring Well Data☐ Other Well Type: _____☐ QA Sample Type: _____

Type of Sample:

☒ Low Concentration☐ High Concentration

SAMPLING DATA:

Date: <u>1-19-00</u>	Color	pH	S.C.	Temp.	Turbidity	DO	Eh	Salinity
Time: <u>1433</u>	Visual	Standard	mS/cm	Degrees C	NTU	mg/l	mV	ppt
Method: <u>Low Flow/Bladder Pump</u>	<u>CLEAR</u>	<u>6.91</u>	<u>34.40</u>	<u>11.8</u>	<u>0.5</u>	<u>5.04</u>	<u>-235</u>	<u>21.61</u>

PURGE DATA:

Date: 1-19-00Method: Low Flow/Bladder PumpMonitor Reading (ppm): —

Well Casing Diameter & Material

Type: 2 PVCTotal Well Depth (TD): 85.0'Static Water Level (WL): 3.44'One Casing Volume(gal): 13.2Start Purge (hrs): 1330End Purge (hrs): 1430Total Purge Time (min): 60Total Vol. Purged (gal): 7.6See Attached Low Flow Purge Data Sheet
for Purge Data

SAMPLE COLLECTION INFORMATION:

Analysis	Preservative	Container Requirements	Collected
TCL VOLATILES (LOW-LEVEL)	HCL / 4° C	40 ml Vial	✓
TCL SEMIVOLATILES	4° C	Qt. Amber Glass	✓
TCL PEST/PCBs	4° C	Qt. Amber Glass	✓
TCL PAH	4° C	Qt. Amber Glass	✓
TAL METALS (TOTAL)	HNO ₃ / 4° C	L PE	✓
TAL METALS (DISSOLVED)	HNO ₃ / 4° C	L PE	✓ (SW)

OBSERVATIONS:

FINAL H₂O LEVEL = 4.11 FT.

Circle if Applicable:

MS/MSD

Duplicate ID No.: _____

Signature(s):

Scott W. Neil



Tetra Tech NUS, Inc.

LOW FLOW PURGE DATA SHEET

Well No.: 6MW11D

PROJECT: NSB-NLON, DRMD
 PROJECT NUMBER: 7363
 SITE: DRMU

DATE: 1-19-00
 WEATHER: Clear, Windy, Cold, Low 20's.
 PERSONNEL: SCOTT NEIL

Well Screen Depth: 75.0 / 85.0 ft.
 Initial Water Level: 3.94 @ 1330 hrs.

Pump Type/Material: BLADDER/PVC
 Pump Intake Depth: 82.0 TWC

Tide Cycle: ☐ High @
☒ Low @ 1429
☐ Not Affected

Total Purge Volume= 7.6 (gal/L)Total Purge Time= 60 (min)

Time	Water Level feet below TOC	Volume mL	Flow Rate mL/min	Pump Settings	Temp °C	pH	Sp Cond mS/cm	DO mg/L	Turbidity NTU	Salinity ppt	Eh mV	Comments
1330	3.94	—	—	35R/25D 50 PSI	—	—	—	—	—	—	—	Start Purging.
1335	4.03	560	480		10.2	6.99	34.50	2.33	4.0	21.59	-177	
1340	4.03				10.9	6.95	34.48	1.50	2.1	21.57	-181	
1345	4.04				11.0	6.94	34.49	2.32	0.9	21.65	-192	
1350	4.06				11.5	6.94	34.50	2.71	0.8	21.66	-208	
1355	4.06				11.6	6.93	34.51	4.21	0.6	21.66	-221	
1400	4.07				11.4	6.93	34.55	4.28	0.7	21.69	-219	
1405	4.07				11.5	6.93	34.53	4.50	0.6	21.71	-220	
1410	4.09				11.4	6.90	34.59	4.77	0.7	21.74	-224	
1415	4.10				11.6	6.92	34.52	4.68	0.6	21.68	-228	
1420	4.09				11.7	6.92	34.48	4.84	0.6	21.66	-232	
1425	4.10				11.7	6.91	34.42	4.89	0.3	21.63	-232	
1430	4.10	↓	↓	↓	11.8	6.91	34.40	5.04	0.5	21.61	-235	END PURGING
	BEGIN SAMPLING @ 1433; Sample ID # DRMD-6MW11D-GW-07.											
	END SAMPLING @ 1454.											

Water Quality Meter (S/N): YSI (193933R)Control Box Type (S/N): QED (15800)Turbidimeter (S/N): LA MOTTE (0639-1298)

Notes: Attempted to begin purging at 1315, however
the tubing inside the well casing was frozen.

"Unlogged" ice in tubing and began purging @ 1330.
 Page 3 of 2

APPENDIX F

CHAIN-OF-CUSTODY RECORDS



DRMO CTO 267
CHAIN OF CUSTODY NUMBER

NUMBER 011800-07

PAGE 1 OF 1

[illegible]



DRMO CTO 267
CHAIN OF CUSTODY

NUMBER 011900-07

PAGE 1 OF 1

[illegible]



TETRA TECH NUS, INC.

CHAIN OF CUSTODY

NUMBER 012100-07

PAGE 1 OF 1

DRMO

PROJECT NO: 7363		SITE NAME: NSB-NUN		PROJECT MANAGER AND PHONE NUMBER MARK MINGEL 412 921 8723				LABORATORY NAME AND CONTACT: ACCUTEST					
SAMPLERS (SIGNATURE) K. S. Simpson				FIELD OPERATIONS LEADER AND PHONE NUMBER KEITH SIMPSON 412 921 8131				ADDRESS 2235 ROUTE 130					
				CARRIER/WAYBILL NUMBER ACCUTEST PICK-UP				CITY, STATE DAYTON, NJ 08810					
				CONTAINER TYPE PLASTIC (P) or GLASS (G) PRESERVATIVE USED									
STANDARD TAT <input checked="" type="checkbox"/> RUSH TAT <input type="checkbox"/> <input type="checkbox"/> 24 hr. <input type="checkbox"/> 48 hr. <input type="checkbox"/> 72 hr. <input type="checkbox"/> 7 day <input type="checkbox"/> 14 day						TYPE OF ANALYSIS							
DATE YEAR 2000	TIME	SAMPLE ID	MATRIX	GRAB (G) COMP (C)	No. OF CONTAINERS	TCL VOC	40 ML VIAL	TCL SVOC (L)	TCL PAH (L)	TCL PEST/PCB (L)	TOTAL TCL METALS (L)	HN03 P	COMMENTS
1/21	0700	GW TB-012100	AG	G	2								1st BLANK
1/21	1525	DRMO 6MW15 GW 07	GW	G	10	3	2	2	2	1			
1. RELINQUISHED BY K. S. Simpson		DATE 1-24-00	TIME 0715	1. RECEIVED BY [Signature]		DATE 1/24/00	TIME 0715	2. RECEIVED BY [Signature]		DATE	TIME		
2. RELINQUISHED BY		DATE	TIME	3. RECEIVED BY		DATE	TIME						
3. RELINQUISHED BY		DATE	TIME										
COMMENTS													

APPENDIX G

DATA VALIDATION LETTERS AND LABORATORY DATA SHEETS



EPC-00-014

TO: MARK MENGEL

DATE: MARCH 29, 2000

FROM: KATHY A. LANDKROHN

COPIES: DV FILE

SUBJECT: ORGANIC DATA VALIDATION: VOA/PEST/PCB
CTO 267, NSB NEW LONDON
SDG E62315

SAMPLES: 13/Aqueous/

DRMO-6MW10D-GW-07
DRMO-6MW11S-GW-07
DRMO-6MW6D-GW-07
GWFD-011900

DRMO-6MW10S-GW-07
DRMO-6MW2D-GW-07
DRMO-6MW6S-GW-07
GWTB-011800

DRMO-6MW11D-GW-07
DRMO-6MW2S-GW-07
DRMO-6MW9S-GW-07
GWTB-011900

Overview

The sample set for the CTO 267, NSB New London, SDG E62315 consists of ten (10) aqueous environmental samples and two (2) trip blanks. Environmental samples were analyzed for volatile organic compounds and pesticides/polychlorinated biphenyls (PCBs). The trip blanks, designated GWTB, were analyzed for volatile organic compounds only. One field duplicate pair was included in the SDG: DRMO-6MW9S-GW-07 and GWFD-011900. The field crew designated sample DRMO-6MW10D-GW-07 for Matrix Spike/Matrix Spike Duplicate (MS/MSD) analysis.

The samples were collected by TetraTech NUS on January 18, 19, and 20, 2000 and analyzed by Accutest Laboratories. Analyses were conducted using the Contract Laboratory Program (CLP) Statement of Work (SOW) OLC02.1 analytical and reporting protocols.

The data were evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- * • GC/MS Tuning
- * • Calibration
- * • Blanks
- * • Surrogate Spike Recoveries
- * • Field Duplicate Precision
- * • Internal Standards Performance
- * • Instrument Performance
- * • Compound Identification
- * • Compound Quantitation
- * • Tentatively Identified Compounds (TICs)

The asterisk (*) indicates that all quality control criteria were met for this parameter. Qualified (if applicable) analytical results are summarized in Appendix A. Results as reported by the laboratory are presented in Appendix B. Appendix C contains Region I worksheets, and Appendix D contains the documentation to support the findings as discussed in this data validation report.

CALIBRATIONS

The following tables summarize calibration non-compliances and corresponding actions:

<u>Compound</u>	<u>IC</u> <u>01/26/00</u>	<u>CC</u> <u>01/27/00</u>
Bromomethane		X

Associated Samples: GWTB-011900

Calibration Actions:

D - Percent Relative Standard Deviation > 30%, Estimated (UJ) nondetected results.
X - Percent Difference > 25%; Estimate (J) positive and (UJ) nondetected results.
R - Relative Response Factors < 0.05; Reject (R) nondetected results and estimated, (J) positive.

SURROGATE RECOVERY

Surrogate recoveries of decachlorobiphenyl were reported above the upper quality control limit on one column in the pesticide/PCB fraction for samples GWFD-01190, DRMO-6MW9S-GW-07, DRMO-6MW11S-GW-07, DRMO-6MW11D-GW-07, DRMO-6MW6S-GW-07, and DRMO-6MW6D-GW-07. Surrogate recoveries reported for the second column of these same samples were reported within the quality control limit. Nondetected results were not qualified as a result of this noncompliance.

BLANK SPIKE RECOVERIES

The percent recovery (%R) of the Blank Spike analyzed on 02/04/2000 was less than the lower quality control limit for Endosulfan sulfate. Nondetected results for samples DRMO-6MW10D-GW-07, DRMO-6MW10S-GW-07, DRMO-6MW6D-GW-07, and DRMO-6MW6S-GW-07 were qualified as estimated, UJ.

ADDITIONAL COMMENTS

Positive results reported at concentrations below the CRQL were qualified as estimated, J.

The presence of methylene chloride in samples DRMO-6MW2S-GW-07 and DRMO-6MW6D-GW-07 is considered to be a laboratory contaminant by the data reviewer. The concentration in both samples is below the CRQL and no action was taken.

The %R of the Blank Spike analyzed on 02/07/2000 was greater than the upper quality control limit for Endrin. No action was taken based on this noncompliance.

The text of this report has been formulated to address only those problem areas affecting data quality.

OVERALL ASSESSMENT

Laboratory Performance: The laboratory was unable to obtain acceptable percent differences between initial and continuing calibration response factors for one volatile compound. Surrogate recoveries for six samples in the pesticide/PCB fraction was above the upper quality control limit. Blank spike recoveries for one pesticide compound were below the quality control limit for four samples.


Other Factors Affecting Data Quality: None.

MEMO TO: M. MENGEL
DATE: MARCH 29, 2000 - PAGE 3


EPC-00-014

The data for these analyses were reviewed with reference to the Region I EPA "Volatile and Semivolatile Data Validation Functional Guidelines - Part II" (12/96).

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."



TetraTech NUS
Kathy A. Landkrohn
Environmental Scientist



TetraTech NUS
Joseph A. Samchuck
Data Validation Quality Assurance Officer

Attachments:

1. Appendix A - Qualified Analytical Results
2. Appendix B - Results as Reported by the Laboratory
3. Appendix C - Regional Worksheets
4. Appendix D - Support Documentation

NSB NEW LONDON

SDG E62315

TABLE I. Summary of Tentatively Identified Volatile Compounds

TIC (DRMO-xxxxxx-GW-07)	6MW10D	6MW10S	6MW11D	6MW11S	6MW2D
Ethene, chlorotrifluoro-	X				
Ethane, 1,2-dichloro-1,1,2-trifluoro	X				
Ethane, 1,1,2-trichloro-1,2,2-trifluoro	X				
4-6-2000 JHJ TIC (DRMO-xxxxxx-GW-07)	6MW2S	6MW6D	6MW6S	6MW9S	GWFD-011900

APPENDIX A

QUALIFIED LABORATORY RESULTS

CTO267 - NSB NEW LONDON
WATER DATA
Accutest, NJ
SDG: E62315

Page 2

SAMPLE NUMBER:
SAMPLE DATE:
LABORATORY ID:
QC_TYPE:
% SOLIDS:
UNITS:
FIELD DUPLICATE OF:

DRMO-6MW10D-GW-07
01/18/00
E62315-4
NORMAL
0.0 %
UG/L

DRMO-6MW10S-GW-07
01/18/00
E62315-5
NORMAL
0.0 %
UG/L

DRMO-6MW11D-GW-07
01/19/00
E62315-10
NORMAL
0.0 %
UG/L

DRMO-6MW11S-GW-07
01/19/00
E62315-9
NORMAL
0.0 %
UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
VOLATILES												
TOLUENE	1	U		1	U		1	U		1	U	
TRANS-1,2-DICHLOROETHENE	1	U		1	U		1	U		1	U	
TRANS-1,3-DICHLOROPROPENE	1	U		1	U		1	U		1	U	
TRICHLOROETHENE	5			1	U		1	U		1	U	
VINYL CHLORIDE	1	U		1	U		1	U		1	U	
XYLENES, TOTAL	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

4

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07

01/20/00

E62315-12

NORMAL

0.0 %

UG/L

DRMO-6MW2S-GW-07

01/20/00

E62315-11

NORMAL

0.0 %

UG/L

DRMO-6MW6D-GW-07

01/18/00

E62315-3

NORMAL

0.0 %

UG/L

DRMO-6MW6S-GW-07

01/18/00

E62315-2

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
VOLATILES												
TOLUENE	1	U		1	U		1	U		1	U	
TRANS-1,2-DICHLOROETHENE	1	U		1	U		1	U		1	U	
TRANS-1,3-DICHLOROPROPENE	1	U		1	U		1	U		1	U	
TRICHLOROETHENE	1	U		1	U		9			0.5	J	P
VINYL CHLORIDE	0.8	J	P	1	U		1	U		1	U	
XYLENES, TOTAL	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

6

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW9S-GW-07

01/19/00

E62315-8

NORMAL

0.0 %

UG/L

GWFD-011900

01/19/00

E62315-7

NORMAL

0.0 %

UG/L

DRMO-GMW9S-GW-07

GWTB-011800

01/18/00

E62315-1

NORMAL

0.0 %

UG/L

GWTB-011900

01/19/00

E62315-6

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
VOLATILES												
TOLUENE	1	U		1	U		1	U		1	U	
TRANS-1,2-DICHLOROETHENE	1	U		1	U		1	U		1	U	
TRANS-1,3-DICHLOROPROPENE	1	U		1	U		1	U		1	U	
TRICHLOROETHENE	1	U		1	U		1	U		1	U	
VINYL CHLORIDE	1	U		1	U		1	U		1	U	
XYLENES, TOTAL	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

1

SAMPLE NUMBER:

DRMO-6MW10D-GW-07

SAMPLE DATE:

01/18/00

LABORATORY ID:

E62315-4

QC_TYPE:

NORMAL

% SOLIDS:

0.0 %

UNITS:

UG/L

FIELD DUPLICATE OF:

DRMO-6MW10S-GW-07

01/18/00

E62315-5

NORMAL

0.0 %

UG/L

DRMO-6MW11D-GW-07

01/19/00

E62315-10

NORMAL

0.0 %

UG/L

DRMO-6MW11S-GW-07

01/19/00

E62315-9

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
PESTICIDES/PCBs												
4,4'-DDD	0.02	U		0.02	U		0.02	U		0.02	U	
4,4'-DDE	0.02	U		0.02	U		0.02	U		0.02	U	
4,4'-DDT	0.02	U		0.02	U		0.02	U		0.02	U	
ALDRIN	0.01	U		0.01	U		0.01	U		0.01	U	
ALPHA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
ALPHA-CHLORDANE	0.01	U		0.01	U		0.01	U		0.01	U	
AROCLOR-1016	0.2	U		0.2	U		0.2	U		0.2	U	
AROCLOR-1221	0.4	U		0.4	U		0.4	U		0.4	U	
AROCLOR-1232	0.2	U		0.2	U		0.2	U		0.2	U	
AROCLOR-1242	0.2	U		0.2	U		0.2	U		0.2	U	
AROCLOR-1248	0.2	U		0.2	U		0.2	U		0.2	U	
AROCLOR-1254	0.2	U		0.2	U		0.2	U		0.2	U	
AROCLOR-1260	0.2	U		0.2	U		0.2	U		0.2	U	
BETA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
DELTA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
DIELDRIN	0.02	U		0.02	U		0.02	U		0.02	U	
ENDOSULFAN I	0.01	U		0.01	U		0.01	U		0.01	U	
ENDOSULFAN II	0.02	U		0.02	U		0.02	U		0.02	U	
ENDOSULFAN SULFATE	0.02	UJ	E	0.02	UJ	E	0.02	U		0.02	U	
ENDRIN	0.02	U		0.02	U		0.02	U		0.02	U	
ENDRIN ALDEHYDE	0.02	U		0.02	U		0.02	U		0.02	U	
ENDRIN KETONE	0.02	U		0.02	U		0.02	U		0.02	U	
GAMMA-BHC (LINDANE)	0.01	U		0.01	U		0.01	U		0.01	U	
GAMMA-CHLORDANE	0.01	U		0.01	U		0.01	U		0.01	U	
HEPTACHLOR	0.01	U		0.01	U		0.01	U		0.01	U	
HEPTACHLOR EPOXIDE	0.01	U		0.01	U		0.01	U		0.01	U	
METHOXYCHLOR	0.1	U		0.1	U		0.1	U		0.1	U	
TOXAPHENE	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

2

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07

01/20/00

E62315-12

NORMAL

0.0 %

UG/L

DRMO-6MW2S-GW-07

01/20/00

E62315-11

NORMAL

0.0 %

UG/L

DRMO-6MW6D-GW-07

01/18/00

E62315-3

NORMAL

0.0 %

UG/L

DRMO-6MW6S-GW-07

01/18/00

E62315-2

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
PESTICIDES/PCBs												
4,4'-DDD	0.021	U		0.021	U		0.021	U		0.02	U	
4,4'-DDE	0.021	U		0.021	U		0.021	U		0.02	U	
4,4'-DDT	0.021	U		0.021	U		0.021	U		0.02	U	
ALDRIN	0.01	U		0.01	U		0.01	U		0.01	U	
ALPHA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
ALPHA-CHLORDANE	0.01	U		0.01	U		0.01	U		0.01	U	
AROCLOR-1016	0.21	U		0.21	U		0.21	U		0.2	U	
AROCLOR-1221	0.41	U		0.42	U		0.42	U		0.4	U	
AROCLOR-1232	0.21	U		0.21	U		0.21	U		0.2	U	
AROCLOR-1242	0.21	U		0.21	U		0.21	U		0.2	U	
AROCLOR-1248	0.21	U		0.21	U		0.21	U		0.2	U	
AROCLOR-1254	0.21	U		0.21	U		0.21	U		0.2	U	
AROCLOR-1260	0.21	U		0.21	U		0.21	U		0.2	U	
BETA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
DELTA-BHC	0.01	U		0.01	U		0.01	U		0.01	U	
DIELDRIN	0.021	U		0.021	U		0.021	U		0.02	U	
ENDOSULFAN I	0.01	U		0.01	U		0.01	U		0.01	U	
ENDOSULFAN II	0.021	U		0.021	U		0.021	U		0.02	U	
ENDOSULFAN SULFATE	0.021	U		0.021	U		0.021	UJ	E	0.02	UJ	E
ENDRIN	0.021	U		0.021	U		0.021	U		0.02	U	
ENDRIN ALDEHYDE	0.021	U		0.021	U		0.021	U		0.02	U	
ENDRIN KETONE	0.021	U		0.021	U		0.021	U		0.02	U	
GAMMA-BHC (LINDANE)	0.01	U		0.01	U		0.01	U		0.01	U	
GAMMA-CHLORDANE	0.01	U		0.01	U		0.01	U		0.01	U	
HEPTACHLOR	0.01	U		0.01	U		0.01	U		0.01	U	
HEPTACHLOR EPOXIDE	0.01	U		0.01	U		0.01	U		0.01	U	
METHOXYCHLOR	0.1	U		0.1	U		0.1	U		0.1	U	
TOXAPHENE	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

3

SAMPLE NUMBER:

DRMO-6MW9S-GW-07

GWFD-011900

SAMPLE DATE:

01/19/00

01/19/00

LABORATORY ID:

E62315-8

E62315-7

QC TYPE:

NORMAL

NORMAL

% SOLIDS:

0.0 %

0.0 %

100.0 %

100.0 %

UNITS:

UG/L

UG/L

FIELD DUPLICATE OF:


DRMO-GMW9S-GW-07

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
PESTICIDES/PCBs												
4,4'-DDD	0.02	U		0.021	U							
4,4'-DDE	0.02	U		0.021	U							
4,4'-DDT	0.02	U		0.021	U							
ALDRIN	0.01	U		0.01	U							
ALPHA-BHC	0.01	U		0.01	U							
ALPHA-CHLORDANE	0.01	U		0.01	U							
AROCLOR-1016	0.2	U		0.21	U							
AROCLOR-1221	0.4	U		0.42	U							
AROCLOR-1232	0.2	U		0.21	U							
AROCLOR-1242	0.2	U		0.21	U							
AROCLOR-1248	0.2	U		0.21	U							
AROCLOR-1254	0.2	U		0.21	U							
AROCLOR-1260	0.2	U		0.21	U							
BETA-BHC	0.01	U		0.01	U							
DELTA-BHC	0.01	U		0.01	U							
DIELDRIN	0.02	U		0.021	U							
ENDOSULFAN I	0.01	U		0.01	U							
ENDOSULFAN II	0.02	U		0.021	U							
ENDOSULFAN SULFATE	0.02	U		0.021	U							
ENDRIN	0.02	U		0.021	U							
ENDRIN ALDEHYDE	0.02	U		0.021	U							
ENDRIN KETONE	0.02	U		0.021	U							
GAMMA-BHC (LINDANE)	0.01	U		0.01	U							
GAMMA-CHLORDANE	0.01	U		0.01	U							
HEPTACHLOR	0.01	U		0.01	U							
HEPTACHLOR EPOXIDE	0.01	U		0.01	U							
METHOXYCHLOR	0.1	U		0.1	U							
TOXAPHENE	1	U		1	U							



Tetra Tech NUS

INTERNAL CORRESPONDENCE

TO: MARK MENGEL  **DATE:** MARCH 30, 2000
FROM: LINDA KARSONOVICH **COPIES:** DV FILE
SUBJECT: ORGANIC DATA VALIDATION: VOA/PEST/PCB
CTO 267, NSB NEW LONDON
SDG E62512

SAMPLES: 2/Aqueous/
DRMO-6MW1S-GW-07 GWTB-012100

Overview

The sample set for the CTO 267, NSB New London, SDG E62512 consists of one (1) aqueous environmental sample and in (1) trip blank. All samples were analyzed for volatile organic compounds. The environmental sample was also analyzed for pesticides/PCBs. No field duplicate pairs were included in the SDG.

The samples were collected by TetraTech NUS on January 21, 2000 and were analyzed by Accutest. Analyses were conducted using CLP SOW OLC02.1 analytical and reporting protocols.

The data were evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- * • GC/MS Tuning
- • Calibration
- * • Blanks
- • Surrogate Spike Recoveries
- * • Internal Standards Performance
- * • Instrument Performance
- * • Compound Identification
- * • Compound Quantitation
- * • Detection Limits

The asterisk (*) indicates that all quality control criteria were met for this parameter. Qualified (if applicable) analytical results are summarized in Appendix A. Results as reported by the laboratory are presented in Appendix B. Appendix C contains Region I worksheets, and Appendix D contains the documentation to support the findings as discussed in this data validation report. The attached Table I summarizes the validation qualifications which were based on the following information:

CALIBRATIONS

The following tables summarize calibration noncompliances and corresponding actions:

<u>Compound</u>	<u>IC</u>	<u>CC</u>
Bromomethane	<u>01/26/00</u>	<u>01/27/00</u>
		X

Associated Samples: All

Calibration Actions:

X - Percent Difference > 25%; Estimate (J) positive and (UJ) nondetected results.

SURROGATE

Surrogate recovery of decachlorobiphenyl exceeded the upper quality control limit on one analytical column in sample DRMO-6MW1S-GW-07. No qualifiers were assigned on this basis since the other was compliant and no target compounds were detected in the sample.

MATRIX SPIKE/MATRIX SPIKE DUPLICATE

Matrix spike recovery of Endrin exceeded the upper quality control limit. No qualifiers were assigned on this basis.

BLANK SPIKE RESULTS

Blank spike recovery of Endrin exceeded the upper quality control limit. No qualifiers were assigned on this basis.

ADDITIONAL COMMENTS

The text of this report has been formulated to address only those problem areas affecting data quality.


OVERALL ASSESSMENT

Laboratory Performance: Bromomethane exceeded the continuing calibration %D criteria.

Other Factors Affecting Data Quality: None.

The data for these analyses were reviewed with reference to the Region I EPA "Volatile and Semivolatile Data Validation Functional Guidelines - Part II" (12/96).

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."



TetraTech NUS

Linda Karsonovich
Chemist/Data Validator



TetraTech NUS

Joseph A. Samchuck
Data Validation Quality Assurance Officer

Attachments:

1. Appendix A - Qualified Analytical Results
2. Appendix B - Results as Reported by the Laboratory
3. Appendix C - Regional Worksheets
4. Appendix D - Support Documentation

NEW LONDON NSB

SDG E62512

TABLE II. Summary of Tentatively Identified Volatile Compounds

TIC

No TICs were reported.

Qualifier Codes:

- A = Lab Blank Contamination
- B = Field Blank Contamination
- C = Calibration (i.e., % RSDs, %Ds, ICVs, CCVs, RPDs, RRFs, etc.) Noncompliance
- D = MS/MSD Noncompliance
- E = LCS/LCSD Noncompliance
- F = Lab Duplicate Imprecision
- G = Field Duplicate Imprecision
- H = Holding Time Exceedance
- I = ICP Serial Dilution Noncompliance
- J = GFAA PDS - GFAA MSA's $r < 0.995$
- K = ICP Interference - include ICSAB % R's
- L = Instrument Calibration Range Exceedance
- M = Sample Preservation
- N = Internal Standard Noncompliance
- O = Poor Instrument Performance (i.e., base-time drifting)
- P = Uncertainty near detection limit ($< 2 \times$ IDL for inorganics and $< \text{CRQL}$ for organics)
- Q = Other problems (can encompass a number of issues)
- R = Surrogates Recovery Noncompliance
- S = Pesticide/PCB Resolution
- T = % Breakdown Noncompliance for DDT and Endrin
- U = Pest/PCB D% between columns for positive results
- V = Non-linear calibrations, tuning $r < 0.995$ (correlation coefficient)
- W = EMPC result
- X = Signal to noise response drop
- Y = % Solid content is less than 30%

APPENDIX A

QUALIFIED LABORATORY RESULTS

CTO267 -NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62512

Page

1

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW1S-GW-07

01/21/00

E62512-2

NORMAL

0.0 %

UG/L

GWTB-012100

01/21/00

E62512-1

NORMAL

0.0 %

UG/L

//

100.0 %

//

100.0 %

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
VOLATILES												
1,1,1-TRICHLOROETHANE	1	U		1	U							
1,1,2,2-TETRACHLOROETHANE	1	U		1	U							
1,1,2-TRICHLOROETHANE	1	U		1	U							
1,1-DICHLOROETHANE	1	U		1	U							
1,1-DICHLOROETHENE	1	U		1	U							
1,2-DIBROMO-3-CHLOROPROPANE	1	U		1	U							
1,2-DIBROMOETHANE	1	U		1	U							
1,2-DICHLOROBENZENE	1	U		1	U							
1,2-DICHLOROETHANE	1	U		1	U							
1,2-DICHLOROPROPANE	1	U		1	U							
1,3-DICHLOROBENZENE	1	U		1	U							
1,4-DICHLOROBENZENE	1	U		1	U							
2-BUTANONE	5	U		5	U							
2-HEXANONE	5	U		5	U							
4-METHYL-2-PENTANONE	5	U		5	U							
ACETONE	5	U		5	U							
BENZENE	1	U		1	U							
BROMOCHLOROMETHANE	1	U		1	U							
BROMODICHLOROMETHANE	1	U		1	U							
BROMOFORM	1	U		1	U							
BROMOMETHANE	1	UJ	C	1	UJ	C						
CARBON DISULFIDE	1	U		1	U							
CARBON TETRACHLORIDE	1	U		1	U							
CHLOROBENZENE	1	U		1	U							
CHLOROETHANE	1	U		1	U							
CHLOROFORM	1	U		1	U							
CHLOROMETHANE	1	U		1	U							
CIS-1,2-DICHLOROETHENE	1	U		1	U							
CIS-1,3-DICHLOROPROPENE	1	U		1	U							
DIBROMOCHLOROMETHANE	1	U		1	U							
ETHYLBENZENE	1	U		1	U							
METHYLENE CHLORIDE	2	U		2	U							
STYRENE	1	U		1	U							
TETRACHLOROETHENE	1	U		1	U							

CTO267 -NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62512

Page 2

SAMPLE NUMBER:

DRMO-6MW1S-GW-07

GWTB-012100

SAMPLE DATE:

01/21/00

01/21/00

LABORATORY ID:

E62512-2

E62512-1

QC_TYPE:

NORMAL

NORMAL

% SOLIDS:

0.0 %

0.0 %

UNITS:

UG/L

UG/L

FIELD DUPLICATE OF:

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
VOLATILES												
TOLUENE	1	U		1	U							
TRANS-1,2-DICHLOROETHENE	1	U		1	U							
TRANS-1,3-DICHLOROPROPENE	1	U		1	U							
TRICHLOROETHENE	1	U		1	U							
VINYL CHLORIDE	1	U		1	U							
XYLENES, TOTAL	1	U		1	U							

SDG: E62512

11

100.0 %

[illegible]



Tetra Tech NUS

INTERNAL CORRESPONDENCE

TO: M. MENGEL **DATE: APRIL 6, 2000**
FROM: GRETCHEN PHIPPS **COPIES: DV FILE**
SUBJECT: ORGANIC DATA VALIDATION – SEMIVOLATILES AND PAHs
CTO 267 - NSB NEW LONDON
SDG – E62315A

SAMPLES: 10/Aqueous/

DRMO-GWMW10D-GW-07
DRMO-GWMW11D-GW-07
DRMO-GWMW2D-GW-07
DRMO-GWMW6D-GW-07
DRMO-GWMW9S-GW-07

DRMO-GWMW10S-GW-07
DRMO-GWMW11S-GW-07
DRMO-GWMW2S-GW-07
DRMO-GWMW6S-GW-07
GWFD-011900

Overview

The sample set for CTO 267, NSB New London, SDG E62315A, consists of ten (10) aqueous environmental samples. One (1) field duplicate pair (DRMO-GWMW9S-GW-07 / GWFD-011900) was included within this SDG.

All samples were analyzed for target compound list (TAL) semivolatile organics and polynuclear aromatic hydrocarbons (PAHs). The samples were collected by Tetra Tech NUS on January 18-20, 2000 and analyzed by Accutest Laboratories under Naval Facilities Engineering Service Center (NFESC) Quality Assurance/Quality Control (QA/QC) criteria. Semivolatile analyses were conducted using SW 846 method 8270C. PAH analyses were conducted using SW 846 method 8310.

The data was evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- * • GC/MS Tuning and System Performance
- * • Initial/Continuing Calibrations
- * • Laboratory Method Blanks
- * • Surrogate Spike Recoveries
- * • Matrix Spike/Matrix Spike Duplicate Results
- * • Blank Spike Results
- * • Internal Standard Performance
- * • Field Duplicate Results
- * • Compound Identification
- * • Compound Quantitation
- * • Detection Limits
- * - All quality control criteria were met for this parameter.

Initial/Continuing Calibrations

The initial calibration on January 4, 2000 contained a %RSD for hexachlorocyclopentadiene that was >30% quality control limit affecting the samples analyzed on instrument GCMSR. The nondetected results reported for hexachlorocyclopentadiene in the affected samples were qualified as estimated, "UJ".

The continuing calibration on January 24, 2000 contained a %D for hexachlorocyclopentadiene that was >25% quality control limit affecting the samples analyzed on instrument GCMSR on 1-24-00. The nondetected results reported for hexachlorocyclopentadiene in the affected samples were qualified as estimated, "UJ".

Matrix Spike/Matrix Spike Duplicate Results

The Matrix Spike/Matrix Spike Duplicate percent recoveries (%Rs) for 4,6-dinitro-2-methylphenol and 3-nitroaniline were less than the lower quality control limits affecting sample GWFD-011900. The relative percent differences (%RPDs) for 2,4-dinitrophenol, 4,6-dinitro-2-methylphenol, 4-chloroaniline and 3-nitroaniline were greater than the upper quality control limits affecting sample GWFD-011900. The nondetected results reported for 2,4-dinitrophenol, 4,6-dinitro-2-methylphenol, 4-chloroaniline and 3-nitroaniline in the affected sample were qualified as estimated, "UJ".

The Matrix Spike/Matrix Spike Duplicate percent recoveries (%Rs) for phenol and 3-nitroaniline were less than the lower quality control limits affecting sample DRMO-GMW10D-GW-07. The relative percent differences (%RPDs) for 4-chloroaniline and 3-nitroaniline were greater than the upper quality control limits affecting sample DRMO-GMW10D-GW-07. The nondetected results reported for phenol, 4-chloroaniline and 3-nitroaniline in the affected sample were qualified as estimated, "UJ".

Blank Spike Results

The Blank Spike %Rs for benzoic acid and phenol were less than the lower quality control limits affecting samples DRMO-GMW11D-GW-07, DRMO-GMW11S-GW-07, DRMO-GMW2D-GW-07, DRMO-GMW2S-GW-07, DRMO-GMW9S-GW-07 and GWFD-011900. The nondetected results reported for benzoic acid and phenol in the affected samples were qualified as estimated, "UJ".

The Blank Spike %Rs for benzoic acid, 3-nitroaniline and phenol were less than the lower quality control limits affecting samples DRMO-GMW10D-GW-07, DRMO-GMW10S-GW-07, DRMO-GMW6D-GW-07 and DRMO-GMW6S-GW-07. The nondetected results reported for benzoic acid, 3-nitroaniline and phenol in the affected samples were qualified as estimated, "UJ".

Notes

The PAH compounds are listed on the semivolatile form 1s. However, they were reported using SW 846 method 8310.

Executive Summary

Laboratory Performance: Hexachlorocyclopentadiene was qualified due to calibration noncompliances.


Other Factors Affecting Data Quality: Several Matrix Spike/Matrix Spike Duplicate and Blank Spike noncompliances were noted.


MEMO TO: M. MENGEL - PAGE 3
DATE: APRIL 6, 2000

The data for these analyses were reviewed with reference to the "National Functional Guidelines for Organic Review Data Review", February 1994, "EPA Region I Volatile/Semivolatile Data Validation Functional Guidelines", December 1996 and the NFESC document entitled "Navy Installation Restoration Laboratory Quality Assurance Guide." (NFESC 2/96).

The text of this report has been formulated to address only those problem areas affecting data quality.

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."


Tetra Tech NUS
Gretchen A. Phipps


Tetra Tech NUS
Joseph A. Samchuck
Quality Control Officer

Attachments:

1. Appendix A - Qualified Analytical Data
2. Appendix B - Results as reported by the Laboratory
3. Appendix C - Regional Worksheets
4. Appendix D - Support Documentation

APPENDIX A
QUALIFIED ANALYTICAL RESULTS

Qualifier Codes:

- A = Lab Blank Contamination
- B = Field Blank Contamination
- C = Calibration (i.e., % RSDs, %Ds, ICVs, CCVs, RPDs, RRFs, etc.) Noncompliance
- D = MS/MSD Noncompliance
- E = LCS/LCSD Noncompliance
- F = Lab Duplicate Imprecision
- G = Field Duplicate Imprecision
- H = Holding Time Exceedance
- I = ICP Serial Dilution Noncompliance
- J = GFAA PDS - GFAA MSA's $r < 0.995$
- K = ICP Interference - include ICSAB % R's
- L = Instrument Calibration Range Exceedance
- M = Sample Preservation
- N = Internal Standard Noncompliance
- O = Poor Instrument Performance (i.e., base-time drifting)
- P = Uncertainty near detection limit ($< 2 \times$ IDL for inorganics and $< \text{CRQL}$ for organics)
- Q = Other problems (can encompass a number of issues)
- R = Surrogates Recovery Noncompliance
- S = Pesticide/PCB Resolution
- T = % Breakdown Noncompliance for DDT and Endrin
- U = Pest/PCD% between columns for positive results
- V = Non-linear calibrations, tuning $r < 0.995$ (correlation coefficient)
- W = EMPC result
- X = Signal to noise response drop

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315A

Page

2

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW10D-GW-07

01/18/00

E62315-4A

NORMAL

0.0 %

UG/L

DRMO-6MW10S-GW-07

01/18/00

E62315-5A

NORMAL

0.0 %

UG/L

DRMO-6MW11D-GW-07

01/19/00

E62315-10A

NORMAL

0.0 %

UG/L

DRMO-6MW11S-GW-07

01/19/00

E62315-9A

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
SEMIVOLATILES												
DI-N-OCTYL PHTHALATE	2.1	U		2	U		2	U		2	U	
DIBENZOFURAN	5.2	U		5	U		5	U		5	U	
DIETHYL PHTHALATE	2.1	U		2	U		2	U		2	U	
DIMETHYL PHTHALATE	2.1	U		2	U		2	U		2	U	
HEXACHLOROBENZENE	2.1	U		2	U		2	U		2	U	
HEXACHLOROBUTADIENE	5.2	U		5	U		5	U		5	U	
HEXACHLOROCYCLOPENTADIENE	21	UJ	C	20	UJ	C	20	U		20	U	
HEXACHLOROETHANE	5.2	U		5	U		5	U		5	U	
ISOPHORONE	2.1	U		2	U		2	U		2	U	
N-NITROSO-DI-N-PROPYLAMINE	5.2	U		5	U		5	U		5	U	
N-NITROSODIPHENYLAMINE	5.2	U		5	U		5	U		5	U	
NITROBENZENE	2.1	U		2	U		2	U		2	U	
PENTACHLOROPHENOL	21	U		20	U		20	U		20	U	
PHENOL	5.2	UJ	DE	5	UJ	E	5	UJ	E	5	UJ	E

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315A

Page

3

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07

01/20/00

E62315-12A

NORMAL

0.0 %

UG/L

DRMO-6MW2S-GW-07

01/20/00

E62315-11A

NORMAL

0.0 %

UG/L

DRMO-6MW6D-GW-07

01/18/00

E62315-3A

NORMAL

0.0 %

UG/L

DRMO-6MW6S-GW-07

01/18/00

E62315-2A

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
SEMIVOLATILES												
1,2,4-TRICHLOROBENZENE	2	U		2	U		2.1	U		2	U	
1,2-DICHLOROBENZENE	2	U		2	U		2.1	U		2	U	
1,3-DICHLOROBENZENE	2	U		2	U		2.1	U		2	U	
1,4-DICHLOROBENZENE	2	U		2	U		2.1	U		2	U	
2,4,5-TRICHLOROPHENOL	5	U		5	U		5.3	U		5.1	U	
2,4,6-TRICHLOROPHENOL	5	U		5	U		5.3	U		5.1	U	
2,4-DICHLOROPHENOL	5	U		5	U		5.3	U		5.1	U	
2,4-DIMETHYLPHENOL	5	U		5	U		5.3	U		5.1	U	
2,4-DINITROPHENOL	20	U		20	U		21	U		20	U	
2,4-DINITROTOLUENE	2	U		2	U		2.1	U		2	U	
2,6-DINITROTOLUENE	2	U		2	U		2.1	U		2	U	
2-CHLORONAPHTHALENE	5	U		5	U		5.3	U		5.1	U	
2-CHLOROPHENOL	5	U		5	U		5.3	U		5.1	U	
2-METHYLPHENOL	5	U		5	U		5.3	U		5.1	U	
2-NITROANILINE	5	U		5	U		5.3	U		5.1	U	
2-NITROPHENOL	5	U		5	U		5.3	U		5.1	U	
3&4-METHYLPHENOL	5	U		5	U		5.3	U		5.1	U	
3,3'-DICHLOROBENZIDINE	5	U		5	U		5.3	U		5.1	U	
3-NITROANILINE	5	U		5	U		5.3	UJ	E	5.1	UJ	E
4,6-DINITRO-2-METHYLPHENOL	20	U		20	U		21	U		20	U	
4-BROMOPHENYL PHENYL ETHER	2	U		2	U		2.1	U		2	U	
4-CHLORO-3-METHYLPHENOL	5	U		5	U		5.3	U		5.1	U	
4-CHLOROANILINE	5	U		5	U		5.3	U		5.1	U	
4-CHLOROPHENYL PHENYL ETHER	2	U		2	U		2.1	U		2	U	
4-NITROANILINE	5	U		5	U		5.3	U		5.1	U	
4-NITROPHENOL	20	U		20	U		21	U		20	U	
BENZOIC ACID	20	UJ	E	20	UJ	E	21	UJ	E	20	UJ	E
BIS(2-CHLOROETHOXY)METHANE	2	U		2	U		2.1	U		2	U	
BIS(2-CHLOROETHYL)ETHER	2	U		2	U		2.1	U		2	U	
BIS(2-CHLOROISOPROPYL) ETHER	2	U		2	U		2.1	U		2	U	
BIS(2-ETHYLHEXYL)PHTHALATE	2	U		2	U		2.1	U		2	U	
BUTYLBENZYL PHTHALATE	2	U		2	U		2.1	U		2	U	
CARBAZOLE	2	U		2	U		2.1	U		2	U	
DIMETHYL PHTHALATE							2.1	U		2	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315A

Page

4

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07

01/20/00

E62315-12A

NORMAL

0.0 %

UG/L

DRMO-6MW2S-GW-07

01/20/00

E62315-11A

NORMAL

0.0 %

UG/L

DRMO-6MW6D-GW-07

01/18/00

E62315-3A

NORMAL

0.0 %

UG/L

DRMO-6MW6S-GW-07

01/18/00

E62315-2A

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
SEMIVOLATILES												
DI-N-OCTYL PHTHALATE	2	U		2	U		2.1	U		2	U	
DIBENZOFURAN	5	U		5	U		5.3	U		5.1	U	
DIETHYL PHTHALATE	2	U		2	U		2.1	U		2	U	
DIMETHYL PHTHALATE	2	U		2	U		2.1	U		2	U	
HEXACHLOROBENZENE	2	U		2	U		2.1	U		2	U	
HEXACHLOROBUTADIENE	5	U		5	U		5.3	U		5.1	U	
HEXACHLOROCYCLOPENTADIENE	20	U		20	U		21	UJ	C	20	UJ	C
HEXACHLOROETHANE	5	U		5	U		5.3	U		5.1	U	
ISOPHORONE	2	U		2	U		2.1	U		2	U	
N-NITROSO-DI-N-PROPYLAMINE	5	U		5	U		5.3	U		5.1	U	
N-NITROSODIPHENYLAMINE	5	U		5	U		5.3	U		5.1	U	
NITROBENZENE	2	U		2	U		2.1	U		2	U	
PENTACHLOROPHENOL	20	U		20	U		21	U		20	U	
PHENOL	5	UJ	E	5	UJ	E	5.3	UJ	E	5.1	UJ	E

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315A

Page

6

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW9S-GW-07

01/19/00

E62315-8A

NORMAL

0.0 %

UG/L

GWFD-011900

01/19/00

E62315-7A

NORMAL

0.0 %

UG/L

DRMO-GMW9S-GW-07

//

100.0 %

//

100.0 %

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
SEMIVOLATILES												
DI-N-OCTYL PHTHALATE	2.1	U		2.1	U							
DIBENZOFURAN	5.2	U		5.2	U							
DIETHYL PHTHALATE	2.1	U		2.1	U							
DIMETHYL PHTHALATE	2.1	U		2.1	U							
HEXACHLOROBENZENE	2.1	U		2.1	U							
HEXACHLOROBUTADIENE	5.2	U		5.2	U							
HEXACHLOROCYCLOPENTADIENE	21	U		21	U							
HEXACHLOROETHANE	5.2	U		5.2	U							
ISOPHORONE	2.1	U		2.1	U							
N-NITROSO-DI-N-PROPYLAMINE	5.2	U		5.2	U							
N-NITROSODIPHENYLAMINE	5.2	U		5.2	U							
NITROBENZENE	2.1	U		2.1	U							
PENTACHLOROPHENOL	21	U		21	U							
PHENOL	5.2	UJ	E	5.2	UJ	E						

CTO267 - NSB NEW LONDON
WATER DATA

Accutest, NJ

SDG: E62315A

Page

1

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW10D-GW-07

01/18/00

E62315-4A

NORMAL

0.0 %

UG/L

DRMO-6MW10S-GW-07

01/18/00

E62315-5A

NORMAL

0.0 %

UG/L

DRMO-6MW11D-GW-07

01/19/00

E62315-10A

NORMAL

0.0 %

UG/L

DRMO-6MW11S-GW-07

01/19/00

E62315-9A

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
POLYNUCLEAR AROMATIC HYDROCARBONS												
1-METHYLNAPHTHALENE	1.1	U		1	U		1	U		1.1	U	
2-METHYLNAPHTHALENE	1.1	U		1	U		1	U		1.1	U	
ACENAPHTHENE	1.1	U		1	U		1	U		1.1	U	
ACENAPHTHYLENE	1.1	U		1	U		1	U		1.1	U	
ANTHRACENE	1.1	U		1	U		1	U		1.1	U	
BENZO(A)ANTHRACENE	0.16	U		0.15	U		0.15	U		0.16	U	
BENZO(A)PYRENE	0.16	U		0.15	U		0.15	U		0.16	U	
BENZO(B)FLUORANTHENE	0.16	U		0.15	U		0.15	U		0.16	U	
BENZO(G,H,I)PERYLENE	0.16	U		0.15	U		0.15	U		0.16	U	
BENZO(K)FLUORANTHENE	0.16	U		0.15	U		0.15	U		0.16	U	
CHRYSENE	0.16	U		0.15	U		0.15	U		0.16	U	
DIBENZO(A,H)ANTHRACENE	0.16	U		0.15	U		0.15	U		0.16	U	
FLUORANTHENE	1.1	U		1	U		1	U		1.1	U	
FLUORENE	1.1	U		1	U		1	U		1.1	U	
INDENO(1,2,3-CD)PYRENE	0.16	U		0.15	U		0.15	U		0.16	U	
NAPHTHALENE	1.1	U		1	U		1	U		1.1	U	
PHENANTHRENE	1.1	U		1	U		1	U		1.1	U	
PYRENE	1.1	U		1	U		1	U		1.1	U	

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315A

Page

2

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07

01/20/00

E62315-12A

NORMAL

0.0 %

UG/L

DRMO-6MW2S-GW-07

01/20/00

E62315-11A

NORMAL

0.0 %

UG/L

DRMO-6MW6D-GW-07

01/18/00

E62315-3A

NORMAL

0.0 %

UG/L

DRMO-6MW6S-GW-07

01/18/00

E62315-2A

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
POLYNUCLEAR AROMATIC HYDROCARBONS												
1-METHYLNAPHTHALENE	1	U		1	U		1	U		1	U	
2-METHYLNAPHTHALENE	1	U		1	U		1	U		1	U	
ACENAPHTHENE	1	U		1	U		1	U		1	U	
ACENAPHTHYLENE	1	U		1	U		1	U		1	U	
ANTHRACENE	1	U		1	U		1	U		1	U	
BENZO(A)ANTHRACENE	0.15	U		0.15	U		0.16	U		0.15	U	
BENZO(A)PYRENE	0.15	U		0.15	U		0.16	U		0.15	U	
BENZO(B)FLUORANTHENE	0.15	U		0.15	U		0.16	U		0.15	U	
BENZO(G,H,I)PERYLENE	0.15	U		0.15	U		0.16	U		0.15	U	
BENZO(K)FLUORANTHENE	0.15	U		0.15	U		0.16	U		0.15	U	
CHRYSENE	0.15	U		0.15	U		0.16	U		0.15	U	
DIBENZO(A,H)ANTHRACENE	0.15	U		0.15	U		0.16	U		0.15	U	
FLUORANTHENE	1	U		1	U		1	U		1	U	
FLUORENE	1	U		1	U		1	U		1	U	
INDENO(1,2,3-CD)PYRENE	0.15	U		0.15	U		0.16	U		0.15	U	
NAPHTHALENE	1	U		1	U		1	U		1	U	
PHENANTHRENE	1	U		1	U		1	U		1	U	
PYRENE	1	U		1	U		1	U		1	U	

CTO267 - NSB NEW LONDON
WATER DATA
Accutest, NJ
SDG: E62315A

Page

3

SAMPLE NUMBER:

DRMO-6MW9S-GW-07

GWFD-011900

SAMPLE DATE:

01/19/00

01/19/00

LABORATORY ID:

E62315-8A

E62315-7A

QC_TYPE:

NORMAL

NORMAL

% SOLIDS:

0.0 %

0.0 %

UNITS:

UG/L

UG/L

FIELD DUPLICATE OF:

DRMO-GMW9S-GW-07

100.0 %


100.0 %

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
POLYNUCLEAR AROMATIC HYDROCARBONS												
1-METHYLNAPHTHALENE	1.1	U		1.1	U							
2-METHYLNAPHTHALENE	1.1	U		1.1	U							
ACENAPHTHENE	1.1	U		1.1	U							
ACENAPHTHYLENE	1.1	U		1.1	U							
ANTHRACENE	1.1	U		1.1	U							
BENZO(A)ANTHRACENE	0.16	U		0.16	U							
BENZO(A)PYRENE	0.16	U		0.16	U							
BENZO(B)FLUORANTHENE	0.16	U		0.16	U							
BENZO(G,H,I)PERYLENE	0.16	U		0.16	U							
BENZO(K)FLUORANTHENE	0.16	U		0.16	U							
CHRYSENE	0.16	U		0.16	U							
DIBENZO(A,H)ANTHRACENE	0.16	U		0.16	U							
FLUORANTHENE	1.1	U		1.1	U							
FLUORENE	1.1	U		1.1	U							
INDENO(1,2,3-CD)PYRENE	0.16	U		0.16	U							
NAPHTHALENE	1.1	U		1.1	U							
PHENANTHRENE	1.1	U		1.1	U							
PYRENE	1.1	U		1.1	U							



Tetra Tech NUS

INTERNAL CORRESPONDENCE

TO: MARK MENGEL  **DATE:** APRIL 7, 2000

FROM: LINDA KARSONOVICH **COPIES:** DV FILE

SUBJECT: ORGANIC DATA VALIDATION: SVOA/PAH
CTO 267, NEW LONDON
SDG E62512A

SAMPLES: 1/Aqueous/
DRMO-6MW1S-GW-07

Overview

The sample set for the CTO 267, New London, SDG E62512A consists of one (1) aqueous environmental sample. The sample was analyzed for selected semivolatile organic compounds and polynuclear aromatic hydrocarbons (PAH). No field duplicate pairs were included in the SDG.

The sample was collected by TetraTech NUS on January 21, 2000 and were analyzed by Accutest. Analyses were conducted using SW-846 Methods 8270C and 8310 analytical and reporting protocols.

The data were evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- * • GC/MS Tuning
- * • Calibration
- * • Blanks
- * • Surrogate Spike Recoveries
- * • Matrix Spike/Matrix Spike Duplicate Results
- * • Blank Spike Results
- * • Field Duplicate Precision
- * • Internal Standards Performance
- * • Instrument Performance
- * • Compound Identification
- * • Compound Quantitation
- * • Detection Limits

The asterisk (*) indicates that all quality control criteria were met for this parameter. Qualified (if applicable) analytical results are summarized in Appendix A. Results as reported by the laboratory are presented in Appendix B. Appendix C contains Region I worksheets, and Appendix D contains the documentation to support the findings as discussed in this data validation report. The attached Table I summarizes the validation qualifications which were based on the following information:

MATRIX SPIKE/MATRIX SPIKE DUPLICATE

Several compounds fell below the lower quality control limits in the semivolatile MS/MSD. The compounds were not detected in the unspiked sample. The unspiked sample was not included in this SDG. No qualifiers were assigned on this basis.

BLANK SPIKE RESULTS

Several compounds fell below the lower quality control limits in the semivolatile blank spikes. The compounds were not detected in the unspiked samples. Nondetected results for 4,6-dinitro-2-methylphenol, pentachlorophenol, 3,3'-dichlorobenzidine, and 3-nitroaniline were qualified as estimated, UJ.

ADDITIONAL COMMENTS

Positive results reported at concentrations below the CRQL were qualified as estimated, (J).

The quantitation report for the semivolatile fraction of the sample was not in the SDG. The laboratory was contacted and was able to supply the missing information.

The text of this report has been formulated to address only those problem areas affecting data quality.

OVERALL ASSESSMENT

Laboratory Performance: All data quality parameters were met for this fraction. No qualifiers were assigned.


Other Factors Affecting Data Quality: None.

The data for these analyses were reviewed with reference to the Region I EPA "Volatile and Semivolatile Data Validation Functional Guidelines - Part II" (12/96).

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."


TetraTech NUS

Linda Karsonovich
Chemist/Data Validator


TetraTech NUS

Joseph A. Samchuck
Data Validation Quality Assurance Officer

Attachments:

1. Appendix A - Qualified Analytical Results
2. Appendix B - Results as Reported by the Laboratory
3. Appendix C - Regional Worksheets
4. Appendix D - Support Documentation

Qualifier Codes:

- A = Lab Blank Contamination
- B = Field Blank Contamination
- C = Calibration (i.e., % RSDs, %Ds, ICVs, CCVs, RPDs, RRFs, etc.) Noncompliance
- D = MS/MSD Noncompliance
- E = LCS/LCSD Noncompliance
- F = Lab Duplicate Imprecision
- G = Field Duplicate Imprecision
- H = Holding Time Exceedance
- I = ICP Serial Dilution Noncompliance
- J = GFAA PDS - GFAA MSA's $r < 0.995$
- K = ICP Interference - include ICSAB % R's
- L = Instrument Calibration Range Exceedance
- M = Sample Preservation
- N = Internal Standard Noncompliance
- O = Poor Instrument Performance (i.e., base-time drifting)
- P = Uncertainty near detection limit ($< 2 \times$ IDL for inorganics and $< \text{CRQL}$ for organics)
- Q = Other problems (can encompass a number of issues)
- R = Surrogates Recovery Noncompliance
- S = Pesticide/PCB Resolution
- T = % Breakdown Noncompliance for DDT and Endrin
- U = Pest/PCB D% between columns for positive results
- V = Non-linear calibrations, tuning $r < 0.995$ (correlation coefficient)
- W = EMPC result
- X = Signal to noise response drop
- Y = % Solid content is less than 30%

APPENDIX A

QUALIFIED LABORATORY RESULTS



Tetra Tech NUS

INTERNAL CORRESPONDENCE

TO: M. MENGEL

DATE: MARCH 28, 2000

FROM: TERRI L. SOLOMON

COPIES: DV FILE

**SUBJECT: INORGANIC DATA VALIDATION - METALS
CTO 267 - NSB NEW LONDON, CONNECTICUT
SDG - E62315**

SAMPLES: 10/Aqueous/

DRMO-6MW10D-GW-07
DRMO-6MW11S-GW-07
DRMO-6MW6D-GW-07
GWFD-011900

DRMO-6MW10S-GW-07
DRMO-6MW2D-GW-07
DRMO-6MW6S-GW-07

DRMO-6MW11D-GW-07
DRMO-6MW2S-GW-07
DRMO-6MW9S-GW-07

Overview

The sample set for CTO 267, NSB New London, SDG E62315, consists of ten (10) aqueous environmental samples. One (1) field duplicate pair (DRMO-6MW9S-GW-07 / GWFD-011900) was included within this SDG.

All samples were analyzed for Analyte List (TAL) metals. The samples were collected by Tetra Tech NUS on January 18, 19 and 20, 2000 and analyzed by Accutest laboratories under Naval Facilities Engineering Service Center (NFESC) Quality Assurance/Quality Control (QA/QC) criteria. The TAL metals analyses were conducted using "USEPA Contract Laboratory Program Statement of Work for Inorganics Analysis", document ILM04.0. All analyses, with the exception of mercury, were conducted using Inductively Coupled Plasma (ICP) methodologies. Mercury analyses were conducted using Cold Vapor Atomic Absorption (CVAA). These data were evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- Calibration Verifications
- Laboratory Blank Analyses
- Interference Check Sample Analyses
- Matrix Spike Results
- * • Laboratory Duplicate Results
- * • Field Duplicate Results
- Serial Dilution Analyses
- * • Detection Limits
- * • Sample Quantitation
- * - All quality control criteria were met for this parameter.

MEMO TO: M. MENGEL
DATE: MARCH 28, 2000 - PAGE 2

Calibration Verifications

The Contract Required Detection Limit (CRDL) Percent Recoveries (%Rs) for arsenic and zinc were > 120% quality control limit. Positive results < 3X CRDL reported for the aforementioned analytes were qualified as estimated, "J".

The CRDL %R for silver was < 80% quality control limit. The nondetected results reported for the aforementioned analyte were qualified as estimated, "UJ".

Laboratory Blank Analyses

The following contaminants were detected in the laboratory method blanks at the following maximum concentrations:

<u>Analyte</u>	<u>Maximum Concentration</u>	<u>Aqueous Action Level</u>
aluminum	95.6 ug/L	478 ug/L
antimony	2.5 ug/L	12.5 ug/L
beryllium	0.8 ug/L	4.0 ug/L
cadmium	1.0 ug/L	5.0 ug/L
calcium	102.4 ug/L	512 ug/L
chromium	4.3 ug/L	21.5 ug/L
cobalt	1.1 ug/L	5.5 ug/L
copper	1.3 ug/L	6.5 ug/L
iron	56.9 ug/L	284.5 ug/L
lead	1.9 ug/L	9.5 ug/L
magnesium	75.8 ug/L	379 ug/L
manganese	1.3 ug/L	6.5 ug/L
nickel	3.5 ug/L	17.5 ug/L
selenium	6.2 ug/L	31.0 ug/L
sodium	697.2 ug/L	3486 ug/L
thallium	4.4 ug/L	22.0 ug/L
vanadium	1.8 ug/L	9.0 ug/L

Affects samples: All

An action level of 5X the maximum concentration has been used to evaluate the sample data for blank contamination. Dilution factors and sample aliquots were taken into consideration when evaluating for blank contamination. Positive results less than the action level for aluminum, antimony, beryllium, cadmium, chromium, cobalt, copper, iron, lead, manganese, nickel, sodium, thallium and vanadium have been qualified as nondetected, "U". Action was not taken for the remaining analytes as the results were either greater than the action level or were nondetected results.

Interference Check Sample Analyses

The interfering analyte magnesium was present in sample DRMO-6MW10D-GW-07 at a concentration which was comparable to the level of magnesium in the Interference Check Sample (ICS) solution. Several analytes namely arsenic, cadmium, manganese and potassium were present in the ICS solution at concentrations which exceeded 2X the Instrument Detection Limit (IDL). Interference affects exist for arsenic in the affected sample. The positive result reported for arsenic was qualified as estimated, "J".

The interfering analytes calcium and magnesium were present in sample DRMO-6MW11D-GW-07 at concentrations which were comparable to the levels of calcium and magnesium in the Interference Check Sample (ICS) solution. Several analytes namely arsenic, cadmium, manganese and potassium were present in the ICS solution at concentrations which exceeded 2X the Instrument Detection Limit (IDL). Interference affects exist for arsenic and cadmium in the affected sample. The nondetected results reported for arsenic and cadmium were qualified as estimated, "UJ".

MEMO TO: M. MENGEL
DATE: MARCH 28, 2000 - PAGE 3

The interfering analytes calcium and magnesium were present in sample DRMO-6MW2D-GW-07 at concentrations which were comparable to the levels of calcium and magnesium in the Interference Check Sample (ICS) solution. Several analytes namely arsenic, cadmium, manganese and potassium were present in the ICS solution at concentrations which exceeded 2X the Instrument Detection Limit (IDL). Interference affects exist for arsenic in the affected sample. The nondetected result reported for arsenic was qualified as estimated, "UJ".

The interfering analyte magnesium was present in sample DRMO-6MW2S-GW-07 at a concentration which was comparable to the level of magnesium in the Interference Check Sample (ICS) solution. Several analytes namely arsenic, cadmium, manganese and potassium were present in the ICS solution at concentrations which exceeded 2X the Instrument Detection Limit (IDL). Interference affects exist for arsenic and manganese in the affected sample. The positive result reported for manganese and the nondetected result reported for arsenic were qualified as estimated, "J" and "UJ", respectively.

Matrix Spike Results

The matrix spike percent recovery for mercury was < 75% quality control limit. The nondetected results reported for the aforementioned analyte were qualified as estimated, "UJ".

ICP Serial Dilution Results

The ICP serial dilution percent differences for iron, potassium and sodium were > 15% quality control limit. The positive results reported for the aforementioned analytes were qualified as estimated, "J".

Notes

Several CRDL percent recoveries for lead, selenium and thallium were outside the 80-120% quality control limits. However, no validation actions were warranted as all sample results were either nondetects, were > 3X CRDL or were qualified as blank contamination.

Sample results < 2X the Instrument Detection Limit (IDL) for arsenic were qualified as estimated, "J".

Executive Summary

Laboratory Performance: Several CRDL %Rs were outside the 80-120% quality control limits. Several analytes were detected in the laboratory method blanks.


Other Factors Affecting Data Quality: The interfering analytes calcium and/or magnesium were present in several samples. The MS %R for mercury was < 75% quality control limit. The ICP serial dilution percent differences for iron, potassium and sodium were > 15% quality control limit. Sample results < 2X the IDL for arsenic were qualified as estimated.


MEMO TO: M. MENGEL
DATE: MARCH 28, 2000 - PAGE 4

The data for these analyses were reviewed with reference to the "National Functional Guidelines for Inorganic Review", February 1994, "EPA Region I Functional Guidelines for Evaluating Inorganic Analyses", February 1989 and the NFESC document entitled "Navy Installation Restoration Laboratory Quality Assurance Guide" (NFESC 2/96).

The text of this report has been formulated to address only those problem areas affecting data quality.

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."


Zetra Tech NUS
Terri L. Solomon
Chemist


Zetra tech NUS
Joseph A. Samchuck
Quality Assurance Officer

Attachments:

1. Appendix A - Qualified Analytical Results
2. Appendix B - Results as reported by the Laboratory
3. Appendix C - Regional Worksheets
4. Appendix D - Support Documentation

APPENDIX A

Qualified Analytical Results

CTO267 - NSB NEW LONDON
WATER DATA
Accutest, NJ
SDG: E62315

Page 1

SAMPLE NUMBER:

SAMPLE DATE:

LABORATORY ID:

QC_TYPE:

% SOLIDS:

UNITS:

FIELD DUPLICATE OF:

DRMO-6MW10D-GW-07

01/18/00

E62315-4

NORMAL

0.0 %

UG/L

DRMO-6MW10S-GW-07

01/18/00

E62315-5

NORMAL

0.0 %

UG/L

DRMO-6MW11D-GW-07

01/19/00

E62315-10

NORMAL

0.0 %

UG/L

DRMO-6MW11S-GW-07

01/19/00

E62315-9

NORMAL

0.0 %

UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
INORGANICS												
ALUMINUM	72.5	U		72.5	U		274	U	A	261	U	A
ANTIMONY	2.1	U		4.6	U	A	4.6	U	A	2.1	U	
ARSENIC	4.2	J	CKP	2.6	U		2.6	UJ	K	2.6	U	
BARIUM	44.8			127			280			89.4		
BERYLLIUM	0.20	U		0.20	U		0.20	U		0.20	U	
CADMIUM	0.37	U	A	1.2	U	A	0.30	UJ	K	0.64	U	A
CALCIUM	171000			119000			290000			99000		
CHROMIUM	1.0	U		1.0	U		1.0	U		1.0	U	
COBALT	3.3	U	A	2.4	U	A	1.2	U	A	1.4	U	A
COPPER	1.3	U		4.9	U	A	1.9	U	A	5.0	U	A
IRON	1510	J	I	935	J	I	2080	J	I	264	U	A
LEAD	1.8	U		1.8	U		1.8	U		2.7	U	A
MAGNESIUM	384000			247000			769000			237000		
MANGANESE	782			474			1010			344		
MERCURY	0.10	UJ	D	0.10	UJ	D	0.10	UJ	D	0.10	UJ	D
NICKEL	7.9	U	A	35.1			2.4	U	A	1.9	U	
POTASSIUM	175000	J	I	111000	J	I	331000	J	I	103000	J	I
SELENIUM	3.4	U		3.4	U		3.4	U		3.4	U	
SILVER	1.1	UJ	C	1.1	UJ	C	1.1	UJ	C	1.1	UJ	C
SODIUM	2870000	J	I	1780000	J	I	5630000	J	I	1770000	J	I
THALLIUM	4.1	U		4.1	U		4.1	U		4.1	U	
VANADIUM	0.70	U		311			1.5	U	A	20.6		
ZINC	77.6			91.5			8.7	J	C	77.4		

CTO267 - NSB NEW LONDON

WATER DATA

Accutest, NJ

SDG: E62315

Page

2

SAMPLE NUMBER:
SAMPLE DATE:
LABORATORY ID:
QC_TYPE:
% SOLIDS:
UNITS:
FIELD DUPLICATE OF:

DRMO-6MW2D-GW-07
01/20/00
E62315-12
NORMAL
0.0 %
UG/L

DRMO-6MW2S-GW-07
01/20/00
E62315-11
NORMAL
0.0 %
UG/L

DRMO-6MW6D-GW-07
01/18/00
E62315-3
NORMAL
0.0 %
UG/L

DRMO-6MW6S-GW-07
01/18/00
E62315-2
NORMAL
0.0 %
UG/L

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
INORGANICS												
ALUMINUM	1370			327	U	A	130	U	A	104	U	A
ANTIMONY	2.1	U		2.1	U		2.1	U		2.1	U	
ARSENIC	2.6	UJ	K	2.6	UJ	K	2.6	U		2.6	U	
BARIUM	174			28.1			39.3			27.6		
BERYLLIUM	0.20	U		0.20	U		0.20	U		0.20	U	
CADMIUM	0.33	U	A	0.60	U	A	0.45	U	A	0.36	U	A
CALCIUM	252000			165000			69500			10100		
CHROMIUM	2.4	U	A	1.0	U		1.0	U		1.0	U	
COBALT	1.8	U	A	1.7	U	A	1.8	U	A	0.70	U	
COPPER	3.2	U	A	7.5			1.3	U		1.3	U	
IRON	4890	J	I	416	J	I	7150	J	I	75.0	U	A
LEAD	1.8	U		6.1	U	A	1.8	U		1.8	U	
MAGNESIUM	719000			516000			56600			2190		
MANGANESE	687			40.3	J	K	2670			1.8	U	A
MERCURY	0.10	UJ	D	0.10	UJ	D	0.10	UJ	D	0.10	UJ	D
NICKEL	2.9	U	A	3.2	U	A	8.1	U	A	1.9	U	A
POTASSIUM	349000	J	I	230000	J	I	23800	J	I	2570	J	I
SELENIUM	3.4	U		3.4	U		3.4	U		3.4	U	
SILVER	1.1	UJ	C	1.1	UJ	C	1.1	UJ	C	1.1	UJ	C
SODIUM	5580000	J	I	3710000	J	I	431000	J	I	32300	J	I
THALLIUM	4.5	U	A	4.1	U		4.1	U		4.1	U	
VANADIUM	4.8	U	A	5.5	U	A	0.70	U		1.3	U	A
ZINC	27.0	J	C	36.9	J	C	13.3	J	C	3.8	U	

CTO267 - NSB NEW LONDON
WATER DATA
Accutest, NJ
SDG: E62315

Page

3

SAMPLE NUMBER:

DRMO-6MW9S-GW-07

GWFD-011900

SAMPLE DATE:

01/19/00

01/19/00

LABORATORY ID:

E62315-8

E62315-7

QC_TYPE:

NORMAL

NORMAL

% SOLIDS:

0.0 %

0.0 %

UNITS:

UG/L

UG/L

FIELD DUPLICATE OF:

DRMO-GMW9S-GW-07

	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE	RESULT	QUAL	CODE
INORGANICS												
ALUMINUM	310	U	A	340	U	A						
ANTIMONY	2.1	U		2.1	U							
ARSENIC	2.6	U		2.6	U							
BARIUM	14.6			14.4								
BERYLLIUM	0.26	U	A	0.36	U	A						
CADMIUM	0.54	U	A	0.61	U	A						
CALCIUM	1910			1910								
CHROMIUM	1.0	U		1.0	U							
COBALT	5.2	U	A	5.4	U	A						
COPPER	3.0	U	A	2.9	U	A						
IRON	15.4	U		18.9	U	A						
LEAD	1.8	U		1.8	U							
MAGNESIUM	552			551								
MANGANESE	547			549								
MERCURY	0.10	UJ	D	0.10	UJ	D						
NICKEL	4.9	U	A	4.9	U	A						
POTASSIUM	714	J	I	701	J	I						
SELENIUM	3.4	U		3.4	U							
SILVER	1.1	UJ	C	1.1	UJ	C						
SODIUM	3460	U	A	3510	J	I						
THALLIUM	4.1	U		4.1	U							
VANADIUM	1.0	U	A	1.1	U	A						
ZINC	111			120								



Tetra Tech NUS

INTERNAL CORRESPONDENCE

TO: M. MENGEL **DATE:** APRIL 6, 2000
FROM: JENNIFER MALLE **COPIES:** DV FILE
SUBJECT: INORGANIC DATA VALIDATION-TAL METALS
CTO 267 -NSB NEW LONDON
SDG - E62512
SAMPLES: 1/Aqueous/
DRMO-6MW1S-GW-07

Overview

The sample set for CTO 267, NSB, New London, SDG E62512 consists of one (1) aqueous environmental sample.

The sample was analyzed for Target Analyte List (TAL) metals. The sample was collected by Tetra Tech NUS on January 21, 2000 and analyzed by Accutest Laboratories in accordance with Naval Facilities Engineering Service Center (NFESC) Navy Installation Restoration Laboratory Quality Assurance Guide, (February 1996). All metals were analyzed under CLP analytical method ILMO4.0.

The data was evaluated based on the following parameters:

- * • Data Completeness
- * • Holding Times
- Calibration Verification
- Laboratory Blank Analysis
- ICP Interference Analysis
- * • Matrix Spike Recoveries
- * • Laboratory Duplicates
- * • Laboratory Control Sample Recoveries
- ICP Serial Dilution
- * • Sample Quantitation
- * • Detection Limits

* - All quality control criteria were met for this parameter.

Calibration Recoveries

Several Contract Required Detection Limit (CRDL) Percent Recoveries (%Rs) reported for zinc were greater than the 110% quality control limit. The positive result less than three times the CRDL value reported for zinc was qualified as estimated, "J".

Several Contract Required Detection Limit (CRDL) Percent Recoveries (%Rs) reported for arsenic, lead and vanadium were less than the 90% quality control limit. The nondetected results reported for arsenic, lead and vanadium were qualified as estimated, "UJ".

Several Contract Required Detection Limit (CRDL) Percent Recoveries (%Rs) reported for selenium were above and below the 90%-110% quality control limits. The nondetected result reported for selenium was qualified as estimated, "UJ".

Laboratory Blank Analyses

The following contaminants were detected in the laboratory method / preparation blanks at the following maximum concentrations:

Affected samples : All

<u>Analyte</u>	<u>Maximum Concentration</u>	<u>Action Level (aqueous)</u>
Aluminum	106.6 ug/L	533 ug/L
Beryllium	1.0 ug/L	5.0 ug/L
Cadmium	0.90 ug/L	4.5 ug/L
Calcium	97.4 ug/L	487 ug/L
Chromium	5.8 ug/L	29.0 ug/L
Cobalt	1.2 ug/L	6.0 ug/L
Iron ⁽¹⁾	53.32 ug/L	266.6 ug/L
Magnesium	82.1 ug/L	410.5 ug/L
Manganese	1.5 ug/L	7.5 ug/L
Nickel	2.7 ug/L	13.5 ug/L
Vanadium	1.2 ug/L	6.0 ug/L

⁽¹⁾ Maximum concentration present in an aqueous preparation blank

An action level of 5X the maximum concentration was used to evaluate the sample data for blank contamination. Sample aliquot and dilution factors were taken into consideration in evaluation for blank contamination. Positive results less than the action level for cobalt, manganese and nickel were qualified as nondetect, "U", due to laboratory blank contamination. No validation action was required for the remaining analytes as all of the results reported were either greater than the blank action level or previously qualified as nondetects by the laboratory.

ICP Interference Check Sample Results

The interfering analyte magnesium was present in sample DRMW-6MW1S-GW-07 at a concentration which was comparable to the level of magnesium in the Interference Check Sample (ICS) solution. Several analytes namely arsenic, cadmium, copper, lead, manganese, nickel, potassium, selenium, vanadium and zinc were present in the ICS solution at concentrations which exceeded the Instrument Detection Limit (IDL). Interference affects exist for arsenic, selenium, vanadium and zinc in the affected sample. The positive result reported for zinc was qualified as estimated, "J". The nondetected results reported for arsenic, selenium and vanadium were qualified as estimated, "UJ".

The result reported for zinc was less than two times the Instrument Detection Limit (IDL) and therefore should be considered as an estimated value. The positive result reported for zinc was qualified as estimated, "J".

Notes

Several Contract Required Detection Limit (CRDL) Percent Recoveries (%Rs) reported for cadmium, chromium and thallium were greater than the 110% quality control limit. However, validation action was not required since results reported were nondetected and a positive bias did not affect the sample results.

Executive Summary

Laboratory Performance: Several laboratory contaminants were present in the laboratory/preparation blanks. Several analytes were qualified for calibration noncompliances.

Other Factors Affecting Data Quality: The interfering analyte magnesium was present in the one sample contained in this SDG. The result for zinc was less than 2x the IDL.


The data for these analyses were reviewed with reference to the "National Functional Guidelines for Inorganic Review", "EPA Region I Inorganic Data Validation Functional Guidelines", December 1996 and the NFESC document entitled "Navy Installation Restoration Laboratory Quality Assurance Guide " (NFESC 2/96).

The text of this report has been formulated to address only those problem areas affecting data quality.

"I attest that the data referenced herein were validated according to the agreed upon validation criteria as specified in the NFESC Guidelines and the Quality Assurance Project Plan (QAPP)."



Tetra Tech NUS
Jennifer Malle
Environmental Scientist



Tetra Tech NUS
Joseph A. Samchuck
Quality Assurance Officer

Attachments:

1. Appendix A - Qualified Analytical Results
2. Appendix B - Results as reported by the Laboratory
3. Appendix C - Region I Worksheets
4. Appendix D - Support Documentation

APPENDIX A

Qualified Analytical Results

Qualifier Codes:

- A = Lab Blank Contamination
- B = Field Blank Contamination
- C = Calibration (i.e., % RSDs, %Ds, ICVs, CCVs, RPDs, RRFs, etc.) Noncompliance
- D = MS/MSD Noncompliance
- E = LCS/LCSD Noncompliance
- F = Lab Duplicate Imprecision
- G = Field Duplicate Imprecision
- H = Holding Time Exceedance
- I = ICP Serial Dilution Noncompliance
- J = GFAA PDS - GFAA MSA's $r < 0.995$
- K = ICP Interference - include ICSAB % R's
- L = Instrument Calibration Range Exceedance
- M = Sample Preservation
- N = Internal Standard Noncompliance
- O = Poor Instrument Performance (i.e., base-time drifting)
- P = Uncertainty near detection limit ($< 2 \times$ IDL for inorganics and $< \text{CRQL}$ for organics)
- Q = Other problems (can encompass a number of issues)
- R = Surrogates Recovery Noncompliance
- S = Pesticide/PCB Resolution
- T = % Breakdown Noncompliance for DDT and Endrin
- U = Pest/PCB D% between columns for positive results
- V = Non-linear calibrations, tuning $r < 0.995$ (correlation coefficient)
- W = EMPC result
- X = Signal to noise response drop
- Y = % Solid content is less than 30%

